

#### **Physical Monitoring Overview**

Beach Management Agreement (BMA) Annual Stakeholder Meeting

December 4, 2015





## Physical Monitoring Data

- Aerial Photography
- Regional Beach and Bathymetric Surveys
- Construction Surveys and Sand Sand
   Sampling
- Data Analysis and Reporting
- Project Certification



#### **Aerial Photography**

- Collected 2 times per year
- Flight Window Based on Tide, Water Clarity, Cloud Cover and Sea Conditions
- Town and County Initiatives
- Tied to Biological Monitoring Protocol



# Regional Beach and Bathymetric Surveys

- Collected on Annual Basis
- Post Storm
- Construction Projects

#### 2015 Regional Surveys

- North of Town (Inlet) (R-60 to R-75)
- Town (R-76 to R-134)
- County (R-135-R-164)



# Data Review and Analysis

- Annual Monitoring Analysis and Reporting
- Volumes, Shorelines and Sediment Budget
- Project Certification



### Programmatic Improvements


- North Beaches and Inlet Sand Trap
- Morphodynamic Analysis
- Assessment of Project Alternatives (Adaptive Management)
- Reach 7 Interim Profiles



#### **North Beach Surveys**

- 2015 174,000 CY Beach Gain
- 33,000 CY Sand Trap Gain







### Sediment Budget 1990-2015

- Net Gain 133,000 CY/YR
- Placement 201,633 CY/YR
- Net Deficit -68,464 CY/YR





## 2015 Construction Projects


- North Mid-Town Project Segment (364,745 CY)
- South Mid-Town Project Segment (597,842 CY)
- Phipps Park (Truck Haul)
   (68,832 CY)
- Reach 8 Dune (Truck Haul)
   (34,902 CY)




### **Town Wide Surveys**


Comparison - 1990-2015















#### **Physical Monitoring Overview**

Beach Management Agreement (BMA) Annual Stakeholder Meeting

December 4, 2015

