# DEPARTMENT OF ENVIRONMENTAL PROTECTION

SEPTIC TANK DESIGNATED APPROVAL NUMBERS
SEPTIC TANK MANUFACTURERS
run date: 10/9/2026
Searching for: HS20

## A & L Septic Tank Products

Orange

**P. O. Box 677878**
**Orlando, FL 32867**

ACTIVE

| TANK NUMBER | CATEGORY | WALL THICKNESS | LIQUID DEPTH | TOP EXTERIOR WIDTH | TOP EXTERIOR LENGTH | IN-OUT DROP | EFFECTIVE GALLONS | TOTAL GALLONS (Pump Tanks) | USE | APPROVAL DATE | FAMILY |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 48-029-03D-C4 | C4 | 6.00 | 46.00 | 60 | 100 | 2 | 750 | 1,060 | B | 11/9/2010 | |
| REMARKS: HS20 traffic rated, slide-in baffle | | | | | | | | | | | |
| 48-029-03S-C4 | C4 | 6.00 | 46.00 | 60 | 100 | 2 | 750 | 1,060 | B | 11/9/2010 | |
| REMARKS: HS20 traffic rated | | | | | | | | | | | |
| 48-029-10D-C4 | C4 | 6.00 | 48.00 | 72 | 102 | 2 | 1050 | 1,340 | B | 11/2/2015 | |
| REMARKS: HS20 traffic rated, mid-seam, slide-in baffle | | | | | | | | | | | |
| 48-029-10S-C4 | C4 | 6.00 | 48.00 | 72 | 102 | 2 | 1050 | 1,400 | B | 11/2/2015 | |
| REMARKS: HS20 traffic rated, mid-seam | | | | | | | | | | | |
| 48-029-15D-C4 | C4 | 6.00 | 59.00 | 72 | 102 | 2 | 1250 | 1,543 | B | 11/9/2010 | |
| REMARKS: C4 and HS20 traffic rated, mid-seam, slide-in baffle | | | | | | | | | | | |
| 48-029-15S-C4 | C4 | 6.00 | 59.00 | 72 | 102 | 2 | 1250 | 1,543 | B | 11/9/2010 | |
| REMARKS: C4 and HS20 traffic rated | | | | | | | | | | | |

# DEPARTMENT OF ENVIRONMENTAL PROTECTION

SEPTIC TANK DESIGNATED APPROVAL NUMBERS
SEPTIC TANK MANUFACTURERS
run date: 10/9/2026
Searching for: HS20

## AA Precast Products Inc.

Duval

**8300 W. Beaver**
**Jacksonville, FL 32220-2301**

ACTIVE

| TANK NUMBER | CATEGORY | WALL THICKNESS | LIQUID DEPTH | TOP EXTERIOR WIDTH | TOP EXTERIOR LENGTH | IN-OUT DROP | EFFECTIVE GALLONS | TOTAL GALLONS (Pump Tanks) | USE | APPROVAL DATE | FAMILY |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 16-065-03D-C4 | C4 | 6.00 | 32.00 | 48 | 136 | | 750 | 905 | | 2/22/2011 | |
| REMARKS: Tank rated for HS20 traffic | | | | | | | | | | | |
| 16-065-03S-C4 | C4 | 6.00 | 32.00 | 48 | 136 | | 750 | 905 | | 2/22/2011 | |
| REMARKS: Tank rated for HS20 traffic | | | | | | | | | | | |
| 16-065-04D-C4 | C4 | 6.00 | 40.00 | 48 | 136 | | 900 | 1,101 | | 2/22/2011 | |
| REMARKS: Tank rated for HS20 traffic4S | | | | | | | | | | | |
| 16-065-04S-C4 | C4 | 6.00 | 40.00 | 48 | 136 | | 900 | 1,101 | | 2/22/2011 | |
| REMARKS: Tank rated for HS20 traffic | | | | | | | | | | | |
| 16-065-14D-C4 | C4 | 6.00 | 48.00 | 71 | 108 | | 1250 | 1,525 | | 2/22/2011 | |
| REMARKS: Tank rated for HS20 traffic | | | | | | | | | | | |
| 16-065-14S-C4 | C4 | 6.00 | 48.00 | 71 | 108 | | 1250 | 1,525 | | 2/22/2011 | |
| REMARKS: Tank rated for HS20 traffic | | | | | | | | | | | |
| 16-065-15D-C4 | C4 | 6.00 | 47.00 | 60 | 136 | | 1050 | 1,269 | | 1/31/2011 | |
| REMARKS: Also HS20 traffic rating | | | | | | | | | | | |
| 16-065-15S-C4 | C4 | 6.00 | 47.00 | 60 | 136 | | 1050 | 1,307 | | 1/31/2011 | |
| REMARKS: Also HS20 traffic rating | | | | | | | | | | | |
| 16-065-19D-C4 | C4 | 6.00 | 47.00 | 83 | 108 | | 1900 | 2,189 | | 1/31/2011 | |
| REMARKS: Also HS20 rating | | | | | | | | | | | |
| 16-065-19S-C4 | C4 | 6.00 | 47.00 | 83 | 108 | | 1900 | 2,274 | | 1/31/2011 | |
| REMARKS: Also HS20 rating | | | | | | | | | | | |
| 16-065-21D-C4 | C4 | 6.00 | 58.00 | 83 | 108 | | 1500 | 1,830 | | 2/22/2011 | |
| REMARKS: Tank rated for HS20 traffic | | | | | | | | | | | |
| 16-065-21S-C4 | C4 | 6.00 | 58.00 | 83 | 108 | | 1500 | 1,830 | | 2/22/2011 | |
| REMARKS: Tank rated for HS20 traffic | | | | | | | | | | | |
| 16-065-41D-C4 | C4 | 6.00 | 63.00 | 83 | 157 | | 2500 | 3,096 | | 2/22/2011 | |
| REMARKS: Tank rated for HS20 traffic | | | | | | | | | | | |
| 16-065-41S-C4 | C4 | 6.00 | 63.00 | 83 | 157 | | 2500 | 3,096 | | 2/22/2011 | |
| REMARKS: Tank rated for HS20 traffic | | | | | | | | | | | |

## DEPARTMENT OF ENVIRONMENTAL PROTECTION

SEPTIC TANK DESIGNATED APPROVAL NUMBERS
SEPTIC TANK MANUFACTURERS
run date: 10/9/2026
Searching for: HS20

# All American Precast Manufacturing

Dade

**1300 NW 4th Street**
**Homestead FL 33030**

ACTIVE

| TANK NUMBER | CATEGORY | WALL THICKNESS | LIQUID DEPTH | TOP EXTERIOR WIDTH | TOP EXTERIOR LENGTH | IN-OUT DROP | EFFECTIVE GALLONS | TOTAL GALLONS (Pump Tanks) | USE | APPROVAL DATE | FAMILY |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 13-159-07D-C4 | C4 | 6.00 | 63.00 | 54 | 84 | 2.5 | 750 | 860 | GI | 12/9/2020 | |
| REMARKS: Secondary pour baffle. HS20 traffic loading rated when installed with 2 ft of cover. Approved for use as a grease interceptor only. Lid # 210. Waterstop, watertightness testing per rule 64E-6.013(10)(d), FAC, required. | | | | | | | | | | | |
| 13-159-12D-C4 | C4 | 6.00 | 74.00 | 60 | 108 | 2.5 | 1200 | 1,580 | GI | 12/9/2020 | |
| REMARKS: Secondary pour baffle. HS20 traffic loading rated when installed with 2 ft of cover. Approved for use as a grease interceptor only. Lid # 211. Waterstop, watertightness testing per rule 64E-6.013(10)(d), FAC, required. | | | | | | | | | | | |
| 13-159-15D-C4 | C4 | 6.00 | 62.00 | 84 | 108 | 2.5 | 1500 | 2,010 | GI | 12/9/2020 | |
| REMARKS: Secondary pour baffle. HS20 traffic loading rated when installed with 2 ft of cover. Approved for use as a grease interceptor only. Lid # 212. Waterstop, watertightness testing per rule 64E-6.013(10)(d), FAC, required. | | | | | | | | | | | |
| 13-159-20D-C4 | C4 | 6.00 | 60.00 | 72 | 150 | 2.5 | 2000 | 2,460 | GI | 12/9/2020 | |
| REMARKS: Secondary pour baffle. HS20 traffic loading rated when installed with 2 ft of cover. Approved for use as a grease interceptor only. Lid # 213. Waterstop, watertightness testing per rule 64E-6.013(10)(d), FAC, required. | | | | | | | | | | | |

# DEPARTMENT OF ENVIRONMENTAL PROTECTION

SEPTIC TANK DESIGNATED APPROVAL NUMBERS
SEPTIC TANK MANUFACTURERS
run date: 10/9/2026
Searching for: HS20

## Alpha General Services, Inc.

Highlands

**Post Office Box 3331**
**Sebring, FL 33871**

ACTIVE

| TANK NUMBER | CATEGORY | WALL THICKNESS | LIQUID DEPTH | TOP EXTERIOR WIDTH | TOP EXTERIOR LENGTH | IN-OUT DROP | EFFECTIVE GALLONS | TOTAL GALLONS (Pump Tanks) | USE | APPROVAL DATE | FAMILY |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 28-004-40D-C4 | C4 | 0.50 | 53.75 | 70 | 97 | 2.5 | 750 | | B,GI | 7/29/2013 | |
| REMARKS: HS20 rated with at least 18" burial; no mid-seam test after install needed with Alpha sticker; length+width at inside edge of flange | | | | | | | | | | | |
| 28-004-40S-C4 | C4 | 0.50 | 53.75 | 70 | 97 | 2.5 | 750 | | B,GI | 7/29/2013 | |
| REMARKS: HS20 rated with at least 18" burial; no mid-seam test after install needed with Alpha sticker; length+width at inside edge of flange | | | | | | | | | | | |
| 28-004-41D-C4 | C4 | 0.50 | 57.75 | 70 | 97 | 2.5 | 900 | | B,GI | 7/29/2013 | |
| REMARKS: HS20 rated with at least 18" burial; no mid-seam test after install needed with Alpha sticker; length+width at inside edge of flange | | | | | | | | | | | |
| 28-004-41S-C4 | C4 | 0.50 | 57.75 | 70 | 97 | 2.5 | 900 | | B,GI | 7/29/2013 | |
| REMARKS: HS20 rated with at least 18" burial; no mid-seam test after install needed with Alpha sticker; length+width at inside edge of flange | | | | | | | | | | | |
| 28-004-42D-C4 | C4 | 0.50 | 60.75 | 70 | 103 | 2.5 | 1050 | | B,GI | 7/29/2013 | |
| REMARKS: HS20 rated with at least 18" burial; no mid-seam test after install needed with Alpha sticker; length+width at inside edge of flange | | | | | | | | | | | |
| 28-004-42S-C4 | C4 | 0.50 | 60.75 | 70 | 103 | 2.5 | 1050 | | B,GI | 7/29/2013 | |
| REMARKS: HS20 rated with at least 18" burial; no mid-seam test after install needed with Alpha sticker; length+width at inside edge of flange | | | | | | | | | | | |
| 28-004-43D-C4 | C4 | 0.50 | 55.75 | 70 | 114 | 2.5 | 1200 | | B,GI | 7/29/2013 | |
| REMARKS: HS20 rated with at least 18" burial; mid-seam testing after installation not required when factory testing seal is present; length+width at inside edge of flange | | | | | | | | | | | |
| 28-004-43S-C4 | C4 | 0.50 | 55.75 | 70 | 114 | 2.5 | 1200 | | B,GI | 7/29/2013 | |
| REMARKS: HS20 rated with at least 18" burial; mid-seam testing after installation not required when factory testing seal is present; length+width at inside edge of flange | | | | | | | | | | | |
| 28-004-44D-C4 | C4 | 0.50 | 55.75 | 70 | 125 | 2.5 | 1350 | | B,GI | 7/29/2013 | |
| REMARKS: HS20 rated with at least 18" burial; no mid-seam test after install needed with Alpha sticker; length+width at inside edge of flange | | | | | | | | | | | |
| 28-004-44S-C4 | C4 | 0.50 | 55.75 | 70 | 125 | 2.5 | 1350 | | B | 7/29/2013 | |
| REMARKS: HS20 rated with at least 18" burial; no mid-seam test after install needed with Alpha sticker; length+width at inside edge of flange | | | | | | | | | | | |
| 28-004-45D-C4 | C4 | 0.50 | 54.00 | 70 | 135 | 2.5 | 1500 | | B,GI | 7/29/2013 | |
| REMARKS: HS20 rated with at least 18" burial; no mid-seam test after install needed with Alpha sticker; length+width at inside edge of flange | | | | | | | | | | | |
| 28-004-45S-C4 | C4 | 0.50 | 54.00 | 70 | 135 | 2.5 | 1500 | | B | 7/29/2013 | |
| REMARKS: HS20 rated with at least 18" burial; no mid-seam test after install needed with Alpha sticker; length+width at inside edge of flange | | | | | | | | | | | |
| 28-004-46D-C4 | C4 | 0.50 | 55.75 | 70 | 146 | 2.5 | 1650 | | B,GI | 7/29/2013 | |
| REMARKS: HS20 rated with at least 18" burial; no mid-seam test after install needed with Alpha sticker; length+width at inside edge of flange | | | | | | | | | | | |
| 28-004-46S-C4 | C4 | 0.50 | 55.75 | 70 | 146 | 2.5 | 1650 | | B | 7/29/2013 | |
| REMARKS: HS20 rated with at least 18" burial; no mid-seam test after install needed with Alpha sticker; length+width at inside edge of flange | | | | | | | | | | | |

# DEPARTMENT OF ENVIRONMENTAL PROTECTION

SEPTIC TANK DESIGNATED APPROVAL NUMBERS
SEPTIC TANK MANUFACTURERS
run date: 10/9/2026
Searching for: HS20

## Averett Septic Tank Co.

Polk

**Post Office Box 266**
**Eaton Park, FL 33840**

ACTIVE

| TANK NUMBER | CATEGORY | WALL THICKNESS | LIQUID DEPTH | TOP EXTERIOR WIDTH | TOP EXTERIOR LENGTH | IN-OUT DROP | EFFECTIVE GALLONS | TOTAL GALLONS (Pump Tanks) | USE | APPROVAL DATE | FAMILY |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 53-037-50D-C4 | C4 | 6.00 | 40.00 | 69 | 113 | | 900 | 1,132 | | 3/27/2008 | |
| REMARKS: Slide-in baffle. Rated for AASHTO HS20 traffic. Revised 08/19/2009 | | | | | | | | | | | |
| 53-037-50S-C4 | C4 | 6.00 | 40.00 | 69 | 113 | | 900 | 1,132 | | 3/27/2008 | |
| REMARKS: Rated for AASHTO HS20 traffic. Revised 08/19/2009 | | | | | | | | | | | |
| 53-037-51D-C4 | C4 | 6.00 | 45.50 | 69.5 | 113.5 | | 1050 | 1,273 | | 3/27/2008 | |
| REMARKS: Slide-in baffle. Rated for AASHTO HS20 traffic. Revised 08/19/2009 | | | | | | | | | | | |
| 53-037-51S-C4 | C4 | 6.00 | 45.50 | 69.5 | 113.5 | | 1050 | 1,273 | | 3/27/2008 | |
| REMARKS: Rated for AASHTO HS20 traffic. Revised 08/19/2009 | | | | | | | | | | | |
| 53-037-52D-C4 | C4 | 6.00 | 52.38 | 70.5 | 114.25 | | 1250 | 1,467 | | 3/27/2008 | |
| REMARKS: Slide-in baffle. Rated for AASHTO HS20 traffic. Revised 08/19/2009 | | | | | | | | | | | |
| 53-037-52S-C4 | C4 | 6.00 | 52.38 | 70.5 | 114.25 | | 1250 | 1,467 | | 3/27/2008 | |
| REMARKS: Rated for AASHTO HS20 traffic. Revised 08/19/2009 | | | | | | | | | | | |

# DEPARTMENT OF ENVIRONMENTAL PROTECTION

SEPTIC TANK DESIGNATED APPROVAL NUMBERS
SEPTIC TANK MANUFACTURERS
run date: 10/9/2026
Searching for: HS20

## Bates Precast Concrete, Incorporated

**6431 Ocean Pond Avenue**
**Lake Park, GA 31636**

ACTIVE

| TANK NUMBER | CATEGORY | WALL THICKNESS | LIQUID DEPTH | TOP EXTERIOR WIDTH | TOP EXTERIOR LENGTH | IN-OUT DROP | EFFECTIVE GALLONS | TOTAL GALLONS (Pump Tanks) | USE | APPROVAL DATE | FAMILY |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 61-074-10D-C4 | C4 | 6.00 | 42.25 | 84 | 96 | 2.5 | 1050 | 1,250 | b,gi | 10/20/2015 | 3 |
| REMARKS: mid-seam; slide-in baffle; HS20, when installed with 1.5 to 4 ft of cover | | | | | | | | | | | |
| 61-074-10S-C4 | C4 | 6.00 | 42.25 | 84 | 96 | 2.5 | 1100 | 1,300 | b,gi | 10/20/2015 | 3 |
| REMARKS: mid-seam; HS20, when installed with 1.5 to 4 ft of cover | | | | | | | | | | | |
| 61-074-125D-C4 | C4 | 6.00 | 50.25 | 84 | 96 | 2.5 | 1250 | 1,550 | b, GI | 8/23/2019 | |
| REMARKS: Slide-in baffle. Mid-seam; HS20 traffic loading rated when installed with 1.5 to 4 ft of cover. Also approved for use as a grease interceptor. | | | | | | | | | | | |
| 61-074-125G-C4 | C4 | 6.00 | 50.25 | 84 | 96 | 2.5 | 1250 | 1,550 | GI | 8/23/2019 | |
| REMARKS: 2 x 626 gallons compartments; Slide-in baffle. Mid-seam; HS20 traffic loading rated when installed with 1.5 to 4 ft of cover. Grease interceptor. | | | | | | | | | | | |
| 61-074-125S-C4 | C4 | 6.00 | 50.25 | 84 | 96 | 2.5 | 1250 | 1,550 | b | 8/23/2019 | |
| REMARKS: Mid-seam; HS20 traffic loading rated when installed with 1.5 to 4 ft of cover. | | | | | | | | | | | |
| 61-074-12D-C4 | C4 | 6.00 | 48.25 | 84 | 96 | 2.5 | 1200 | 1,400 | b,gi | 10/20/2015 | 3 |
| REMARKS: mid-seam; slide-in baffle; HS20, when installed with 1.5 to 4 ft of cover | | | | | | | | | | | |
| 61-074-12S-C4 | C4 | 6.00 | 48.25 | 84 | 96 | 2.5 | 1250 | 1,450 | b,gi | 10/20/2015 | 3 |
| REMARKS: mid-seam; HS20, when installed with 1.5 to 4 ft of cover | | | | | | | | | | | |
| 61-074-13D-C4 | C4 | 6.00 | 54.25 | 84 | 96 | 2.5 | 1350 | 1,550 | b,gi | 10/20/2015 | 3 |
| REMARKS: mid-seam; slide-in baffle; HS20, when installed with 1.5 to 4 ft of cover | | | | | | | | | | | |
| 61-074-13S-C4 | C4 | 6.00 | 54.25 | 84 | 96 | 2.5 | 1400 | 1,650 | b | 10/20/2015 | 3 |
| REMARKS: mid-seam; HS20, when installed with 1.5 to 4 ft of cover | | | | | | | | | | | |
| 61-074-14D-C4 | C4 | 6.00 | 60.25 | 84 | 96 | 2.5 | 1500 | 1,700 | b,gi | 10/20/2015 | 3 |
| REMARKS: mid-seam; slide-in baffle; HS20, when installed with 1.5 to 4 ft of cover | | | | | | | | | | | |
| 61-074-14S-C4 | C4 | 6.00 | 60.25 | 84 | 96 | 2.5 | 1550 | 1,800 | b | 10/20/2015 | 3 |
| REMARKS: mid-seam; HS20, when installed with 1.5 to 4 ft of cover | | | | | | | | | | | |
| 61-074-16D-C4 | C4 | 6.00 | 66.25 | 84 | 96 | 2.5 | 1650 | 1,900 | b,gi | 10/20/2015 | 3 |
| REMARKS: mid-seam; slide-in baffle; HS20, when installed with 1.5 to 4 ft of cover | | | | | | | | | | | |
| 61-074-16S-C4 | C4 | 6.00 | 66.25 | 84 | 96 | 2.5 | 1700 | 1,950 | b | 10/20/2015 | 3 |
| REMARKS: mid-seam; HS20, when installed with 1.5 to 4 ft of cover | | | | | | | | | | | |
| 61-074-19D-C4 | C4 | 5.00 | 43.75 | 82 | 154 | 2.5 | 1900 | 2,290 | b | 5/17/2016 | 2 |
| REMARKS: mid-seam; slide-in baffle; HS20, when installed with 1.5 to 4 ft of cover; 5000 psi concrete | | | | | | | | | | | |
| 61-074-19S-C4 | C4 | 5.00 | 43.75 | 82 | 154 | 2.5 | 1900 | 2,350 | b | 5/17/2016 | 2 |
| REMARKS: mid-seam; HS20, when installed with 1.5 to 4 ft of cover; 5000 psi concrete | | | | | | | | | | | |
| 61-074-22D-C4 | C4 | 5.00 | 50.50 | 82 | 154 | 2.5 | 2200 | 2,600 | b | 5/17/2016 | 2 |
| REMARKS: mid-seam; slide-in baffle; HS20, when installed with 1.5 to 4 ft of cover; 5000 psi concrete | | | | | | | | | | | |
| 61-074-22S-C4 | C4 | 5.00 | 50.50 | 82 | 154 | 2.5 | 2200 | 2,700 | b | 5/17/2016 | 2 |
| REMARKS: mid-seam; HS20, when installed with 1.5 to 4 ft of cover; 5000 psi concrete | | | | | | | | | | | |

## DEPARTMENT OF ENVIRONMENTAL PROTECTION

SEPTIC TANK DESIGNATED APPROVAL NUMBERS
SEPTIC TANK MANUFACTURERS
run date: 10/9/2026
Searching for: HS20

# Bates Precast Concrete, Incorporated

**6431 Ocean Pond Avenue**
**Lake Park, GA 31636**

ACTIVE

| TANK NUMBER | CATEGORY | WALL THICKNESS | LIQUID DEPTH | TOP EXTERIOR WIDTH | TOP EXTERIOR LENGTH | IN-OUT DROP | EFFECTIVE GALLONS | TOTAL GALLONS (Pump Tanks) | USE | APPROVAL DATE | FAMILY |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 61-074-25D-C4 | C4 | 5.00 | 57.50 | 82 | 154 | 2.5 | 2500 | 3,040 | b | 8/23/2019 | |
| REMARKS: Slide-in baffle. Mid-seam; HS20 traffic loading rated when installed with 1.5 to 3 ft of cover and 5000 psi concrete is used. | | | | | | | | | | | |
| 61-074-25G-C4 | C4 | 5.00 | 57.50 | 82 | 154 | 2.5 | 2500 | 3,040 | GI | 8/23/2019 | |
| REMARKS: 2 x 1250 gallons compartments; Slide-in baffle. Mid-seam; HS20 traffic loading rated when installed with 1.5 to 3 ft of cover and 5000 psi concrete is used. Grease interceptor. | | | | | | | | | | | |
| 61-074-25S-C4 | C4 | 5.00 | 57.50 | 82 | 154 | 2.5 | 2500 | 3,040 | b | 8/23/2019 | |
| REMARKS: Mid-seam; HS20 traffic loading rated when installed with 1.5 to 3 ft of cover and 5000 psi concrete is used. | | | | | | | | | | | |
| 61-074-27D-C4 | C4 | 5.00 | 62.00 | 82 | 154 | 2.5 | 2700 | 3,200 | b | 5/17/2016 | 2 |
| REMARKS: mid-seam; slide-in baffle; HS20, when installed with 1.5 to 4 ft of cover; 5000 psi concrete | | | | | | | | | | | |
| 61-074-27S-C4 | C4 | 5.00 | 62.00 | 82 | 154 | 2.5 | 2700 | 3,290 | b | 5/17/2016 | 2 |
| REMARKS: mid-seam; HS20, when installed with 1.5 to 4 ft of cover; 5000 psi concrete | | | | | | | | | | | |
| 61-074-30D-C4 | C4 | 5.00 | 68.75 | 82 | 154 | 2.5 | 3000 | 3,500 | b | 5/17/2016 | 2 |
| REMARKS: mid-seam; slide-in baffle; HS20, when installed with 1.5 to 4 ft of cover; 5000 psi concrete | | | | | | | | | | | |
| 61-074-30S-C4 | C4 | 5.00 | 68.75 | 82 | 154 | 2.5 | 3000 | 3,600 | b | 5/17/2016 | 2 |
| REMARKS: mid-seam; HS20, when installed with 1.5 to 4 ft of cover; 5000 psi concrete | | | | | | | | | | | |
| 61-074-37D-C4 | C4 | 8.00 | 43.64 | 115 | 235 | 2.5 | 3700 | 4,200 | b | 5/17/2016 | 1 |
| REMARKS: mid-seam; slide-in baffle; HS20, when installed with 1.5 to 4 ft of cover; octogonal shape | | | | | | | | | | | |
| 61-074-37S-C4 | C4 | 8.00 | 43.64 | 115 | 235 | 2.5 | 3700 | 4,300 | b | 5/17/2016 | 1 |
| REMARKS: mid-seam; HS20, when installed with 1.5 to 4 ft of cover; octogonal shape | | | | | | | | | | | |
| 61-074-43D-C4 | C4 | 8.00 | 50.77 | 115 | 235 | 2.5 | 4300 | 4,900 | b | 5/17/2016 | 1 |
| REMARKS: mid-seam; slide-in baffle; HS20, when installed with 1.5 to 4 ft of cover; octogonal shape | | | | | | | | | | | |
| 61-074-43S-C4 | C4 | 8.00 | 50.77 | 115 | 235 | 2.5 | 4300 | 5,000 | b | 5/17/2016 | 1 |
| REMARKS: mid-seam; HS20, when installed with 1.5 to 4 ft of cover; octogonal shape | | | | | | | | | | | |
| 61-074-48D-C4 | C4 | 8.00 | 56.64 | 115 | 235 | 2.5 | 4800 | 5,500 | b | 5/17/2016 | 1 |
| REMARKS: mid-seam; slide-in baffle; HS20, when installed with 1.5 to 4 ft of cover; octogonal shape | | | | | | | | | | | |
| 61-074-48S-C4 | C4 | 8.00 | 56.64 | 115 | 235 | 2.5 | 4800 | 5,600 | b | 5/17/2016 | 1 |
| REMARKS: mid-seam; HS20, when installed with 1.5 to 4 ft of cover; octogonal shape | | | | | | | | | | | |
| 61-074-53D-C4 | C4 | 8.00 | 62.53 | 115 | 235 | 2.5 | 5300 | 6,100 | b | 5/17/2016 | 1 |
| REMARKS: mid-seam; slide-in baffle; HS20, when installed with 1.5 to 4 ft of cover; octogonal shape | | | | | | | | | | | |
| 61-074-53S-C4 | C4 | 8.00 | 62.53 | 115 | 235 | 2.5 | 5300 | 6,200 | b | 5/17/2016 | 1 |
| REMARKS: mid-seam; HS20, when installed with 1.5 to 4 ft of cover; octogonal shape | | | | | | | | | | | |
| 61-074-58D-C4 | C4 | 8.00 | 68.41 | 115 | 235 | 2.5 | 5800 | 6,600 | b | 5/17/2016 | 1 |
| REMARKS: mid-seam; slide-in baffle; HS20, when installed with 1.5 to 4 ft of cover; octogonal shape | | | | | | | | | | | |
| 61-074-58S-C4 | C4 | 8.00 | 68.41 | 115 | 235 | 2.5 | 5800 | 6,800 | b | 5/17/2016 | 1 |
| REMARKS: mid-seam; HS20, when installed with 1.5 to 4 ft of cover; octogonal shape | | | | | | | | | | | |

## DEPARTMENT OF ENVIRONMENTAL PROTECTION

SEPTIC TANK DESIGNATED APPROVAL NUMBERS
SEPTIC TANK MANUFACTURERS
run date: 10/9/2026
Searching for: HS20

# Bates Precast Concrete, Incorporated

**6431 Ocean Pond Avenue**
**Lake Park, GA 31636**

ACTIVE

| TANK NUMBER | CATEGORY | WALL THICKNESS | LIQUID DEPTH | TOP EXTERIOR WIDTH | TOP EXTERIOR LENGTH | IN-OUT DROP | EFFECTIVE GALLONS | TOTAL GALLONS (Pump Tanks) | USE | APPROVAL DATE | FAMILY |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 61-074-63D-C4 | C4 | 8.00 | 74.28 | 115 | 235 | 2.5 | 6300 | 7,200 | b | 5/17/2016 | 1 |
| REMARKS: mid-seam; slide-in baffle; HS20, when installed with 1.5 to 4 ft of cover; octogonal shape | | | | | | | | | | | |
| 61-074-63S-C4 | C4 | 8.00 | 74.28 | 115 | 235 | 2.5 | 6300 | 7,400 | b | 5/17/2016 | 1 |
| REMARKS: mid-seam; HS20, when installed with 1.5 to 4 ft of cover; octogonal shape | | | | | | | | | | | |
| 61-074-68D-C4 | C4 | 8.00 | 80.16 | 115 | 235 | 2.5 | 6800 | 7,800 | b | 5/17/2016 | 1 |
| REMARKS: mid-seam; slide-in baffle; HS20, when installed with 1.5 to 4 ft of cover; octogonal shape | | | | | | | | | | | |
| 61-074-68S-C4 | C4 | 8.00 | 80.16 | 115 | 235 | 2.5 | 6800 | 7,900 | b | 5/17/2016 | 1 |
| REMARKS: mid-seam; HS20, when installed with 1.5 to 4 ft of cover; octogonal shape | | | | | | | | | | | |
| 61-074-71D-C4 | C4 | 8.00 | 83.68 | 115 | 235 | 2.5 | 7100 | 8,100 | b | 5/17/2016 | 1 |
| REMARKS: mid-seam; slide-in baffle; HS20, when installed with 1.5 to 4 ft of cover; octogonal shape | | | | | | | | | | | |
| 61-074-71S-C4 | C4 | 8.00 | 83.68 | 115 | 235 | 2.5 | 7100 | 8,300 | b | 5/17/2016 | 1 |
| REMARKS: mid-seam; HS20, when installed with 1.5 to 4 ft of cover; octogonal shape | | | | | | | | | | | |

# DEPARTMENT OF ENVIRONMENTAL PROTECTION

SEPTIC TANK DESIGNATED APPROVAL NUMBERS
SEPTIC TANK MANUFACTURERS
run date: 10/9/2026
Searching for: HS20

## Del Zotto Mfg. Co.

Marion

**4575 W. Highway 40**
**Ocala, FL 34482**

ACTIVE

| TANK NUMBER | CATEGORY | WALL THICKNESS | LIQUID DEPTH | TOP EXTERIOR WIDTH | TOP EXTERIOR LENGTH | IN-OUT DROP | EFFECTIVE GALLONS | TOTAL GALLONS (Pump Tanks) | USE | APPROVAL DATE | FAMILY |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 42-007-14S-C4 | C4 | 7.00 | 85.00 | 86 | 86 | | 1350 | 1,350 | D | 3/27/2012 | |
| REMARKS: Dosing tank only, circular, 7000 PSI, HS20 traffic loading rated with HS20 lid, post-installation watertightness testing required per 64E-6.013(10)(d) FAC | | | | | | | | | | | |
| 42-007-50D-C4 | C4 | 6.00 | 47.00 | 60 | 96 | | 750 | 1,030 | | 7/6/2009 | |
| REMARKS: 4" or 6" inlets and outlets, HS20 traffic loading rated | | | | | | | | | | | |
| 42-007-50S-C4 | C4 | 6.00 | 47.00 | 60 | 96 | | 750 | 1,030 | | 7/6/2009 | |
| REMARKS: 4" or 6" inlets and outlets, HS20 traffic loading rated | | | | | | | | | | | |
| 42-007-51D-C4 | C4 | 6.00 | 44.00 | 72 | 96 | | 900 | 1,222 | | 7/6/2009 | |
| REMARKS: 4" or 6" inlets and outlets, HS20 traffic loading rated | | | | | | | | | | | |
| 42-007-51S-C4 | C4 | 6.00 | 44.00 | 72 | 96 | | 900 | 1,222 | | 7/6/2009 | |
| REMARKS: 4" or 6" inlets and outlets, HS20 traffic loading rated | | | | | | | | | | | |
| 42-007-52D-C4 | C4 | 6.00 | 46.00 | 72 | 108 | | 1050 | 1,446 | | 7/6/2009 | |
| REMARKS: 4" or 6" inlets and outlets, HS20 traffic loading rated | | | | | | | | | | | |
| 42-007-52S-C4 | C4 | 6.00 | 46.00 | 72 | 108 | | 1050 | 1,446 | | 7/6/2009 | |
| REMARKS: 4" or 6" inlets and outlets, HS20 traffic loading rated | | | | | | | | | | | |
| 42-007-53D-C4 | C4 | 6.00 | 44.00 | 72 | 132 | | 1250 | 1,745 | | 7/6/2009 | |
| REMARKS: 4" or 6" inlets and outlets, HS20 traffic loading rated | | | | | | | | | | | |
| 42-007-53S-C4 | C4 | 6.00 | 44.00 | 72 | 132 | | 1250 | 1,745 | | 7/6/2009 | |
| REMARKS: 4" or 6" inlets and outlets, HS20 traffic loading rated | | | | | | | | | | | |
| 42-007-54D-C4 | C4 | 6.00 | 48.00 | 84 | 162 | | 2000 | 2,805 | | 7/6/2009 | |
| REMARKS: 4" or 6" inlets and outlets, HS20 traffic loading rated | | | | | | | | | | | |
| 42-007-54S-C4 | C4 | 6.00 | 48.00 | 84 | 162 | | 2000 | 2,805 | | 7/6/2009 | |
| REMARKS: 4" or 6" inlets and outlets, HS20 traffic loading rated | | | | | | | | | | | |
| 42-007-55D-C4 | C4 | 6.00 | 64.00 | 84 | 162 | | 2800 | 3,366 | | 7/6/2009 | |
| REMARKS: 4" or 6" inlets and outlets, HS20 traffic loading rated | | | | | | | | | | | |
| 42-007-55S-C4 | C4 | 6.00 | 64.00 | 84 | 162 | | 2800 | 3,366 | | 7/6/2009 | |
| REMARKS: 4" or 6" inlets and outlets, HS20 traffic loading rated | | | | | | | | | | | |
| 42-007-G30D-C4 | C4 | 6.00 | 56.00 | 116.5 | 150.75 | 2.5 | 3000 | 3,750 | ATU | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading; April 2014, changed inlet for 2.5" drop. Can house SludgeHammer S-1000 ATU. Remarks updated 1/29/2025. | | | | | | | | | | | |
| 42-007-G30S-C4 | C4 | 6.00 | 56.00 | 116.5 | 150.75 | 2 | 3000 | 3,888 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading. | | | | | | | | | | | |
| 42-007-G32D-C4 | C4 | 6.00 | 60.00 | 116.8 | 151 | | 3200 | 3,995 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-G32S-C4 | C4 | 6.00 | 60.00 | 116.8 | 151 | | 3200 | 4,144 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |

# DEPARTMENT OF ENVIRONMENTAL PROTECTION

SEPTIC TANK DESIGNATED APPROVAL NUMBERS
SEPTIC TANK MANUFACTURERS
run date: 10/9/2026
Searching for: HS20

## Del Zotto Mfg. Co.

Marion

**4575 W. Highway 40**
**Ocala, FL 34482**

ACTIVE

| TANK NUMBER | CATEGORY | WALL THICKNESS | LIQUID DEPTH | TOP EXTERIOR WIDTH | TOP EXTERIOR LENGTH | IN-OUT DROP | EFFECTIVE GALLONS | TOTAL GALLONS (Pump Tanks) | USE | APPROVAL DATE | FAMILY |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 42-007-G35D-C4 | C4 | 6.00 | 65.00 | 117 | 151 | | 3500 | 4,297 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-G35S-C4 | C4 | 6.00 | 65.00 | 117 | 151 | | 3500 | 4,459 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-G37D-C4 | C4 | 6.00 | 68.00 | 117 | 151 | | 3700 | 4,478 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-G37S-C4 | C4 | 6.00 | 68.00 | 117 | 151 | | 3700 | 4,648 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-G40D-C4 | C4 | 6.00 | 73.00 | 117.4 | 151.5 | | 4000 | 4,257 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-G40S-C4 | C4 | 6.00 | 73.00 | 117.4 | 151.5 | | 4000 | 5,111 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-G43D-C4 | C4 | 6.00 | 78.00 | 117.6 | 151.63 | | 4300 | 5,093 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-G43S-C4 | C4 | 6.00 | 78.00 | 117.6 | 151.63 | | 4300 | 5,291 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-G45D-C4 | C4 | 6.00 | 81.00 | 117.9 | 151.88 | | 4500 | 5,472 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-G45S-C4 | C4 | 6.00 | 81.00 | 117.9 | 151.88 | | 4500 | 5,678 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-G48D-C4 | C4 | 6.00 | 69.00 | 117.1 | 187.38 | | 4800 | 5,778 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-G48S-C4 | C4 | 6.00 | 69.00 | 117.1 | 187.38 | | 4800 | 5,951 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-G50D-C4 | C4 | 6.00 | 72.00 | 117.3 | 187.38 | | 5000 | 6,006 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-G50S-C4 | C4 | 6.00 | 72.00 | 117.3 | 187.38 | | 5000 | 6,187 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-G53D-C4 | C4 | 6.00 | 76.00 | 117.5 | 187.63 | | 5300 | 6,323 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-G53S-C4 | C4 | 6.00 | 76.00 | 117.5 | 187.63 | | 5300 | 6,515 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-G55D-C4 | C4 | 6.00 | 78.00 | 117.6 | 187.63 | | 5500 | 6,476 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |

# DEPARTMENT OF ENVIRONMENTAL PROTECTION

SEPTIC TANK DESIGNATED APPROVAL NUMBERS
SEPTIC TANK MANUFACTURERS
run date: 10/9/2026
Searching for: HS20

## Del Zotto Mfg. Co.

Marion

**4575 W. Highway 40**
**Ocala, FL 34482**

ACTIVE

| TANK NUMBER | CATEGORY | WALL THICKNESS | LIQUID DEPTH | TOP EXTERIOR WIDTH | TOP EXTERIOR LENGTH | IN-OUT DROP | EFFECTIVE GALLONS | TOTAL GALLONS (Pump Tanks) | USE | APPROVAL DATE | FAMILY |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 42-007-G55S-C4 | C4 | 6.00 | 78.00 | 117.6 | 187.63 | | 5500 | 6,674 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-G58D-C4 | C4 | 6.00 | 82.00 | 117.9 | 187.88 | | 5800 | 7,029 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-G58S-C4 | C4 | 6.00 | 82.00 | 117.9 | 187.88 | | 5800 | 7,238 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-G60D-C4 | C4 | 6.00 | 73.00 | 117.4 | 217.5 | | 6000 | 7,173 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-G60S-C4 | C4 | 6.00 | 73.00 | 117.4 | 217.5 | | 6000 | 7,357 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-G65D-C4 | C4 | 6.00 | 78.00 | 117.6 | 217.63 | | 6500 | 7,628 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-G65S-C4 | C4 | 6.00 | 78.00 | 117.6 | 217.63 | | 6500 | 7,826 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-G70D-C4 | C4 | 6.00 | 84.00 | 118 | 218 | | 7000 | 8,465 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-G70S-C4 | C4 | 6.00 | 84.00 | 118 | 218 | | 7000 | 8,679 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-G75D-C4 | C4 | 6.00 | 77.00 | 117.5 | 253.63 | | 7500 | 8,884 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-G75S-C4 | C4 | 6.00 | 77.00 | 117.5 | 253.63 | | 7500 | 9,079 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-G80D-C4 | C4 | 6.00 | 81.00 | 117.9 | 253.88 | | 8000 | 9,670 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-G80S-C4 | C4 | 6.00 | 81.00 | 117.9 | 253.88 | | 8000 | 9,876 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-G85D-C4 | C4 | 6.00 | 77.00 | 117.5 | 283.63 | | 8500 | 10,151 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-G85S-C4 | C4 | 6.00 | 77.00 | 117.5 | 283.63 | | 8500 | 10,308 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-G90D-C4 | C4 | 6.00 | 81.00 | 117.6 | 283.63 | | 9000 | 11,011 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-G90S-C4 | C4 | 6.00 | 81.00 | 117.6 | 283.63 | | 9000 | 11,179 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |

# DEPARTMENT OF ENVIRONMENTAL PROTECTION

SEPTIC TANK DESIGNATED APPROVAL NUMBERS
SEPTIC TANK MANUFACTURERS
run date: 10/9/2026
Searching for: HS20

## Del Zotto Mfg. Co.

Marion

**4575 W. Highway 40**
**Ocala, FL 34482**

ACTIVE

| TANK NUMBER | CATEGORY | WALL THICKNESS | LIQUID DEPTH | TOP EXTERIOR WIDTH | TOP EXTERIOR LENGTH | IN-OUT DROP | EFFECTIVE GALLONS | TOTAL GALLONS (Pump Tanks) | USE | APPROVAL DATE | FAMILY |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 42-007-G95D-C4 | C4 | 6.00 | 76.00 | 117.5 | 319.63 | | 9500 | 11,382 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-G95S-C4 | C4 | 6.00 | 76.00 | 117.5 | 319.63 | | 9500 | 11,536 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-GA1D-C4 | C4 | 6.00 | 79.00 | 117.6 | 319.75 | | 10000 | 11,687 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-GA1S-C4 | C4 | 6.00 | 79.00 | 117.6 | 319.75 | | 10000 | 11,887 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-GA2D-C4 | C4 | 6.00 | 83.00 | 118 | 320 | | 10500 | 12,669 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-GA2S-C4 | C4 | 6.00 | 83.00 | 118 | 320 | | 10500 | 12,880 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-GA3D-C4 | C4 | 6.00 | 79.00 | 117.6 | 349.75 | | 11000 | 12,853 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-GA3S-C4 | C4 | 6.00 | 79.00 | 117.6 | 349.75 | | 11000 | 13,053 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-GA4D-C4 | C4 | 6.00 | 83.00 | 118 | 349.88 | | 11500 | 13,926 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-GA4S-C4 | C4 | 6.00 | 83.00 | 118 | 349.88 | | 11500 | 14,137 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-GA5D-C4 | C4 | 6.00 | 78.00 | 117.6 | 385.75 | | 12000 | 14,088 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-GA5S-C4 | C4 | 6.00 | 78.00 | 117.6 | 385.75 | | 12000 | 14,286 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-GA6D-C4 | C4 | 6.00 | 81.00 | 117.9 | 385.88 | | 12500 | 15,103 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-GA6S-C4 | C4 | 6.00 | 81.00 | 117.9 | 385.88 | | 12500 | 15,309 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-GA7D-C4 | C4 | 6.00 | 84.00 | 118 | 386 | | 13000 | 15,601 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-GA7S-C4 | C4 | 6.00 | 84.00 | 118 | 386 | | 13000 | 15,815 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-GA8D-C4 | C4 | 6.00 | 82.00 | 117.9 | 409.88 | | 13500 | 16,266 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |

# DEPARTMENT OF ENVIRONMENTAL PROTECTION

SEPTIC TANK DESIGNATED APPROVAL NUMBERS
SEPTIC TANK MANUFACTURERS
run date: 10/9/2026
Searching for: HS20

## Del Zotto Mfg. Co.

Marion

**4575 W. Highway 40**
**Ocala, FL 34482**

ACTIVE

| TANK NUMBER | CATEGORY | WALL THICKNESS | LIQUID DEPTH | TOP EXTERIOR WIDTH | TOP EXTERIOR LENGTH | IN-OUT DROP | EFFECTIVE GALLONS | TOTAL GALLONS (Pump Tanks) | USE | APPROVAL DATE | FAMILY |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 42-007-GA8S-C4 | C4 | 6.00 | 82.00 | 117.9 | 409.88 | | 13500 | 16,475 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-GA9D-C4 | C4 | 6.00 | 78.00 | 117.6 | 445.63 | | 14000 | 16,388 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-GA9S-C4 | C4 | 6.00 | 78.00 | 117.6 | 445.63 | | 14000 | 16,586 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-GB1D-C4 | C4 | 6.00 | 81.00 | 117.9 | 445.88 | | 14500 | 17,366 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-GB1S-C4 | C4 | 6.00 | 81.00 | 117.9 | 445.88 | | 14500 | 17,778 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-GB2D-C4 | C4 | 6.00 | 84.00 | 118 | 446 | | 15000 | 18,152 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading- | | | | | | | | | | | |
| 42-007-GB2S-C4 | C4 | 6.00 | 84.00 | 118 | 446 | | 15000 | 18,366 | | 2/2/2009 | |
| REMARKS: Approved for HS20 traffic loading | | | | | | | | | | | |
| 42-007-H01S-C4 | C4 | 6.00 | 50.00 | 65 | 46 | | 300 | 400 | Pump t | 3/10/2010 | |
| REMARKS: Tank rated for HS20 traffic loading and C4 burial cover. | | | | | | | | | | | |
| 42-007-H02D-C4 | C4 | 6.00 | 42.00 | 65 | 103 | | 750 | 923 | | 3/10/2010 | |
| REMARKS: Tank rated for HS20 traffic loading and C4 burial cover. | | | | | | | | | | | |
| 42-007-H02S-C4 | C4 | 6.00 | 42.00 | 65 | 103 | | 750 | 923 | | 3/10/2010 | |
| REMARKS: Tank rated for HS20 traffic loading and C4 burial cover. | | | | | | | | | | | |
| 42-007-H03D-C4 | C4 | 6.00 | 50.00 | 65 | 103 | | 900 | 1,060 | | 3/10/2010 | |
| REMARKS: Tank rated for HS20 traffic loading and C4 burial cover. | | | | | | | | | | | |
| 42-007-H03S-C4 | C4 | 6.00 | 50.00 | 65 | 103 | | 900 | 1,060 | | 3/10/2010 | |
| REMARKS: Tank rated for HS20 traffic loading and C4 burial cover. | | | | | | | | | | | |
| 42-007-H04D-C4 | C4 | 6.00 | 42.00 | 65 | 141 | | 1050 | 1,314 | | 3/10/2010 | |
| REMARKS: Tank rated for HS20 traffic loading and C4 burial cover | | | | | | | | | | | |
| 42-007-H04S-C4 | C4 | 6.00 | 42.00 | 65 | 141 | | 1050 | 1,314 | | 3/10/2010 | |
| REMARKS: Tank rated for HS20 traffic loading and C4 burial cover | | | | | | | | | | | |
| 42-007-H05D-C4 | C4 | 6.00 | 50.00 | 65 | 141 | | 1250 | 1,512 | | 3/10/2010 | |
| REMARKS: Tank rated for HS20 traffic loading and C4 burial cover | | | | | | | | | | | |
| 42-007-H05S-C4 | C4 | 6.00 | 50.00 | 65 | 141 | | 1250 | 1,512 | | 3/10/2010 | |
| REMARKS: Tank rated for HS20 traffic loading and C4 burial cover | | | | | | | | | | | |
| 42-007-H06D-C4 | C4 | 6.00 | 45.00 | 87 | 113 | | 1350 | 1,469 | | 3/10/2010 | |
| REMARKS: Tank rated for HS20 traffic loading and C4 burial cover | | | | | | | | | | | |

# DEPARTMENT OF ENVIRONMENTAL PROTECTION

SEPTIC TANK DESIGNATED APPROVAL NUMBERS
SEPTIC TANK MANUFACTURERS
run date: 10/9/2026
Searching for: HS20

## Del Zotto Mfg. Co.

Marion

**4575 W. Highway 40**
**Ocala, FL 34482**

ACTIVE

| TANK NUMBER | CATEGORY | WALL THICKNESS | LIQUID DEPTH | TOP EXTERIOR WIDTH | TOP EXTERIOR LENGTH | IN-OUT DROP | EFFECTIVE GALLONS | TOTAL GALLONS (Pump Tanks) | USE | APPROVAL DATE | FAMILY |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 42-007-H06S-C4 | C4 | 6.00 | 45.00 | 87 | 113 | | 1350 | 1,469 | | 3/10/2010 | |
| REMARKS: Tank rated for HS20 traffic loading and C4 burial cover | | | | | | | | | | | |
| 42-007-H07D-C4 | C4 | 6.00 | 50.00 | 87 | 113 | | 1500 | 1,605 | | 3/10/2010 | |
| REMARKS: Tank rated for HS20 traffic loading and C4 burial cover | | | | | | | | | | | |
| 42-007-H07S-C4 | C4 | 6.00 | 50.00 | 87 | 113 | | 1500 | 1,605 | | 3/10/2010 | |
| REMARKS: Tank rated for HS20 traffic loading and C4 burial cover | | | | | | | | | | | |
| 42-007-H08D-C4 | C4 | 6.00 | 55.00 | 87 | 113 | | 1650 | 1,741 | | 3/10/2010 | |
| REMARKS: Tank rated for HS20 traffic loading and C4 burial cover | | | | | | | | | | | |
| 42-007-H08S-C4 | C4 | 6.00 | 55.00 | 87 | 113 | | 1650 | 1,741 | | 3/10/2010 | |
| REMARKS: Tank rated for HS20 traffic loading and C4 burial cover. | | | | | | | | | | | |
| 42-007-H09D-C4 | C4 | 6.00 | 42.00 | 87 | 164 | | 1900 | 2,102 | | 3/10/2010 | |
| REMARKS: Tank rated for HS20 traffic loading and C4 burial cover | | | | | | | | | | | |
| 42-007-H09S-C4 | C4 | 6.00 | 42.00 | 87 | 164 | | 1900 | 2,102 | | 3/10/2010 | |
| REMARKS: Tank rated for HS20 traffic loading and C4 burial cover | | | | | | | | | | | |
| 42-007-H10D-C4 | C4 | 6.00 | 45.00 | 87 | 164 | | 2000 | 2,224 | | 3/10/2010 | |
| REMARKS: Tank rated for HS20 traffic loading and C4 burial cover | | | | | | | | | | | |
| 42-007-H10S-C4 | C4 | 6.00 | 45.00 | 87 | 164 | | 2000 | 2,224 | | 3/10/2010 | |
| REMARKS: Tank rated for HS20 traffic loading and C4 burial cover | | | | | | | | | | | |
| 42-007-H11D-C4 | C4 | 6.00 | 49.00 | 87 | 164 | | 2200 | 2,388 | | 3/10/2010 | |
| REMARKS: Tank rated for HS20 traffic loading and C4 burial cover | | | | | | | | | | | |
| 42-007-H11S-C4 | C4 | 6.00 | 49.00 | 87 | 164 | | 2200 | 2,388 | | 3/10/2010 | |
| REMARKS: Tank rated for HS20 traffic loading and C4 burial cover | | | | | | | | | | | |
| 42-007-H12D-C4 | C4 | 6.00 | 51.00 | 87 | 164 | | 2300 | 2,471 | | 3/10/2010 | |
| REMARKS: Tank rated for HS20 traffic loading and C4 burial cover | | | | | | | | | | | |
| 42-007-H12S-C4 | C4 | 6.00 | 51.00 | 87 | 164 | | 2300 | 2,471 | | 3/10/2010 | |
| REMARKS: Tank rated for HS20 traffic loading and C4 burial cover | | | | | | | | | | | |
| 42-007-H13D-C4 | C4 | 6.00 | 56.00 | 87 | 164 | | 2500 | 2,677 | | 3/10/2010 | |
| REMARKS: Tank rated for HS20 traffic loading and C4 burial cover | | | | | | | | | | | |
| 42-007-H13S-C4 | C4 | 6.00 | 56.00 | 87 | 164 | | 2500 | 2,677 | | 3/10/2010 | |
| REMARKS: Tank rated for HS20 traffic loading and C4 burial cover | | | | | | | | | | | |
| 42-007-H14D-C4 | C4 | 6.00 | 60.00 | 87 | 164 | | 2700 | 2,847 | | 3/10/2010 | |
| REMARKS: Tank rated for HS20 traffic loading and C4 burial cover | | | | | | | | | | | |
| 42-007-H14S-C4 | C4 | 6.00 | 60.00 | 87 | 164 | | 2700 | 2,842 | | 3/10/2010 | |
| REMARKS: Tank rated for HS20 traffic loading and C4 burial cover | | | | | | | | | | | |

# DEPARTMENT OF ENVIRONMENTAL PROTECTION

SEPTIC TANK DESIGNATED APPROVAL NUMBERS
SEPTIC TANK MANUFACTURERS
run date: 10/9/2026
Searching for: HS20

## Del Zotto Mfg. Co.

Marion

**4575 W. Highway 40**
**Ocala, FL 34482**

ACTIVE

| TANK NUMBER | CATEGORY | WALL THICKNESS | LIQUID DEPTH | TOP EXTERIOR WIDTH | TOP EXTERIOR LENGTH | IN-OUT DROP | EFFECTIVE GALLONS | TOTAL GALLONS (Pump Tanks) | USE | APPROVAL DATE | FAMILY |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 42-007-H15D-C4 | C4 | 6.00 | 56.00 | 116.5 | 150.75 | | 3000 | 3,700 | | 5/8/2012 | |
| REMARKS: slide-in baffle attached by manufacturer; designed for HS20 and 6 feet burial depth; 10" lid; 6,000 psi concrete; 4",6"or 8" inlet and outlet | | | | | | | | | | | |
| 42-007-H15S-C4 | C4 | 6.00 | 56.00 | 116.5 | 150.75 | | 3000 | 3,700 | | 5/3/2012 | |
| REMARKS: designed for HS20 and 6 feet burial depth; 10" lid; 6,000 psi concrete; 4",6"or 8" inlet and outlet | | | | | | | | | | | |
| 42-007-H16D-C4 | C4 | 6.00 | 78.00 | 117.6 | 151.63 | | 4300 | 5,000 | | 5/8/2012 | |
| REMARKS: slide-in baffle attached by manufacturer; designed for HS20 and 6 feet burial depth; 10" lid; 6,000 psi concrete; 4",6"or 8" inlet and outlet | | | | | | | | | | | |
| 42-007-H16S-C4 | C4 | 6.00 | 78.00 | 117.6 | 151.63 | | 4300 | 5,000 | | 5/3/2012 | |
| REMARKS: designed for HS20 and 6 feet burial depth; 10" lid; 6,000 psi concrete; 4",6"or 8" inlet and outlet | | | | | | | | | | | |

# DEPARTMENT OF ENVIRONMENTAL PROTECTION

SEPTIC TANK DESIGNATED APPROVAL NUMBERS
SEPTIC TANK MANUFACTURERS
run date: 10/9/2026
Searching for: HS20

## Florida Septic,Inc.

**Post Office Box 545**
**Hawthorne, FL 32640**

Alachua
ACTIVE

| TANK NUMBER | CATEGORY | WALL THICKNESS | LIQUID DEPTH | TOP EXTERIOR WIDTH | TOP EXTERIOR LENGTH | IN-OUT DROP | EFFECTIVE GALLONS | TOTAL GALLONS (Pump Tanks) | USE | APPROVAL DATE | FAMILY |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 01-011-02D-C4 | C4 | 4.00 | 53.00 | 49.25 | 95.5 | 2.5 | 750 | 925 | B, GI | 5/31/2001 | |
| REMARKS: AASHTO HS20 traffic loading rated when buried between 18" to 48" | | | | | | | | | | | |
| 01-011-02S-C4 | C4 | 4.00 | 53.00 | 49.25 | 95.5 | 2.5 | 750 | 925 | B, GI | 5/31/2001 | |
| REMARKS: AASHTO HS20 traffic loading rated when buried between 18" to 48" | | | | | | | | | | | |
| 01-011-06D-C4 | C4 | 6.00 | 53.00 | 53.25 | 99.5 | 2.5 | 750 | 925 | B, GI | 10/31/2001 | |
| REMARKS: AASHTO HS20 traffic loading rated when buried between 18" to 48" | | | | | | | | | | | |
| 01-011-06S-C4 | C4 | 6.00 | 53.00 | 53.25 | 99.5 | 2.5 | 750 | 925 | B, GI | 10/31/2001 | |
| REMARKS: AASHTO HS20 traffic loading rated when buried between 18" to 48" | | | | | | | | | | | |
| 01-011-11D-C4 | C4 | | 44.00 | 72.5 | 104.5 | 2.5 | 1050 | 1,348 | B, GI, | 3/17/2003 | |
| REMARKS: Houses Bionest BNC-400 ATU. Wall thickness can be either 4" or 6". AASHTO HS20 traffic loading rated when buried between 18" to 48" | | | | | | | | | | | |
| 01-011-11S-C4 | C4 | | 44.00 | 72.5 | 104.5 | 2.5 | 1050 | 1,348 | B, GI, | 3/17/2003 | |
| REMARKS: Wall thickness can be either 4" or 6". AASHTO HS20 traffic loading rated when buried between 18" to 48". Approved as pretreatment tank for the AK12S245C ATU (NSF245 certified) when the ATU is housed in the 01-011-AK10-C3. Approved 03/17/2003. Updated 11/19/2024. | | | | | | | | | | | |
| 01-011-13D-C4 | C4 | | 52.00 | 73 | 105 | 2.5 | 1250 | 1,564 | B, GI, | 3/17/2003 | |
| REMARKS: Houses Bionest BNC-500 ATU. Wall thickness can be either 4" or 6". AASHTO HS20 traffic loading rated when buried between 18" to 48" | | | | | | | | | | | |
| 01-011-13S-C4 | C4 | | 52.00 | 73 | 105 | 2.5 | 1250 | 1,564 | B, GI | 3/17/2003 | |
| REMARKS: Wall thickness can be either 4" or 6". AASHTO HS20 traffic loading rated when buried between 18" to 48" | | | | | | | | | | | |
| 01-011-27D-C4 | C4 | 6.00 | 53.00 | 73 | 137 | 2.5 | 1500 | 1,918 | B, GI, | 10/31/2001 | |
| REMARKS: AASHTO HS20 traffic loading rated when buried between 18" to 48". Can house Bionest BNC-600 ATU. Can house SludgeHammer S-400 ATU. Remarks updated 1/29/2025. | | | | | | | | | | | |
| 01-011-27P-C4 | C4 | 6.00 | 53.00 | 73 | 137 | 2.5 | 1500 | 1,918 | D | 2/28/2011 | |
| REMARKS: ASSHTO HS20 traffic loading rated when buried between 18" to 48" | | | | | | | | | | | |
| 01-011-27S-C4 | C4 | 6.00 | 53.00 | 73 | 137 | 2.5 | 1500 | 1,918 | | 10/31/2001 | |
| REMARKS: AASHTO HS20 traffic loading rated when buried between 18" to 48" | | | | | | | | | | | |
| 01-011-29D-C4 | C4 | 4.00 | 44.00 | 75.25 | 151.5 | 2.5 | 1650 | 2,000 | B, GI | 7/30/2001 | |
| REMARKS: AASHTO HS20 traffic loading rated when buried between 18" to 48" | | | | | | | | | | | |
| 01-011-29N-C4 | C4 | 4.00 | 4.00 | 75.25 | 151.5 | 42.5 | 0 | 2,000 | | 10/3/2013 | |
| REMARKS: Modification of 01-011-29S-C4 for Florida Onsite Sewage Nitrogen Reduction Strategy Study. Media tank: liquid level =4"; add flow-through hole in second structural rib. AASHTO HS20 traffic loading rated when buried between 18" to 48" | | | | | | | | | | | |
| 01-011-29P-C4 | C4 | 4.00 | 44.00 | 75.25 | 151.5 | 2.5 | 1650 | 2,000 | D | 2/28/2011 | |
| REMARKS: lowered pass-through hole for dosing tank; AASHTO HS20 traffic loading rated when buried between 18" to 48" | | | | | | | | | | | |
| 01-011-29S-C4 | C4 | 4.00 | 44.00 | 75.25 | 151.5 | 2.5 | 1650 | 2,000 | B | 7/30/2001 | |
| REMARKS: AASHTO HS20 traffic loading rated when buried between 18" to 48" | | | | | | | | | | | |
| 01-011-30D-C4 | C4 | 6.00 | 44.00 | 79.25 | 155.5 | 2.5 | 1650 | 2,000 | B, GI | 5/29/2002 | |
| REMARKS: AASHTO HS20 traffic loading rated when buried between 18" to 48" | | | | | | | | | | | |

# DEPARTMENT OF ENVIRONMENTAL PROTECTION

SEPTIC TANK DESIGNATED APPROVAL NUMBERS
SEPTIC TANK MANUFACTURERS
run date: 10/9/2026
Searching for: HS20

## Florida Septic,Inc.

Alachua

**Post Office Box 545**
**Hawthorne, FL 32640**

ACTIVE

| TANK NUMBER | CATEGORY | WALL THICKNESS | LIQUID DEPTH | TOP EXTERIOR WIDTH | TOP EXTERIOR LENGTH | IN-OUT DROP | EFFECTIVE GALLONS | TOTAL GALLONS (Pump Tanks) | USE | APPROVAL DATE | FAMILY |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 01-011-30P-C4 | C4 | 5.00 | 44.00 | 79.25 | 155.5 | 2.5 | 1650 | 2,000 | D | 2/28/2011 | |
| REMARKS: ASSHTO HS20 traffic rating when buried between 18" to 48" | | | | | | | | | | | |
| 01-011-30S-C4 | C4 | 6.00 | 44.00 | 19.25 | 155.5 | 2.5 | 1650 | 2,000 | | 5/29/2002 | |
| REMARKS: AASHTO HS20 traffic loading rated when buried between 18" to 48" | | | | | | | | | | | |
| 01-011-39D-C4 | C4 | 6.00 | 53.00 | 80.25 | 156.75 | 2.5 | 2000 | 2,400 | B, ATU | 5/29/2002 | |
| REMARKS: AASHTO HS20 traffic loading rated when buried between 18" to 48". Can house Bionest BNC-750 ATU. Can house SludgeHammer S-600 ATU. Remarks updated 1/29/2025. | | | | | | | | | | | |
| 01-011-39P-C4 | C4 | 6.00 | 53.00 | 80.25 | 156.75 | 2.5 | 2000 | 2,400 | D | 2/28/2011 | |
| REMARKS: ASSHTO HS20 traffic rating when buried between 18" to 48" | | | | | | | | | | | |
| 01-011-39S-C4 | C4 | 6.00 | 53.00 | 80.25 | 156.75 | 2.5 | 2000 | 2,400 | | 5/29/2002 | |
| REMARKS: AASHTO HS20 traffic loading rated when buried between 18" to 48" | | | | | | | | | | | |
| 01-011-49D-C4 | C4 | 6.00 | 65.50 | 82 | 158.5 | 2.5 | 2500 | 3,023 | ATU | 5/29/2002 | |
| REMARKS: AASHTO HS20 traffic loading rated when buried between 18" to 48". Can house SludgeHammer S-800 ATU. Remarks updated 1/29/2025. | | | | | | | | | | | |
| 01-011-49P-C4 | C4 | 6.00 | 65.50 | 82 | 158.5 | 2.5 | 2500 | 3,023 | D | 2/28/2011 | |
| REMARKS: AASHTO HS20 traffic rating when buried between 18" to 48" | | | | | | | | | | | |
| 01-011-49S-C4 | C4 | 6.00 | 65.50 | 82 | 158.5 | 2.5 | 2500 | 3,023 | | 5/29/2002 | |
| REMARKS: AASHTO HS20 traffic loading rated when buried between 18" to 48" | | | | | | | | | | | |
| 01-011-53D-C4 | C4 | 6.00 | 42.50 | 103.3 | 190.75 | 2.5 | 2800 | 3,518 | B | 10/31/2001 | |
| REMARKS: AASHTO HS20 traffic loading rated when buried between 18" to 48" | | | | | | | | | | | |
| 01-011-53P-C4 | C4 | 6.00 | 42.50 | 103.3 | 190.75 | 2.5 | 2800 | 3,518 | D | 2/28/2011 | |
| REMARKS: ASSHTO HS20 traffic rating when buried between 18" to 48" | | | | | | | | | | | |
| 01-011-53S-C4 | C4 | 6.00 | 42.50 | 103.3 | 190.75 | 2.5 | 2800 | 3,518 | | 10/31/2001 | |
| REMARKS: AASHTO HS20 traffic loading rated when buried between 18" to 48" | | | | | | | | | | | |
| 01-011-57D-C4 | C4 | 6.00 | 45.50 | 103.5 | 191.63 | 2.5 | 3000 | 3,733 | B, ATU | 10/31/2001 | |
| REMARKS: AASHTO HS20 traffic loading rated when buried between 18" to 48". Can house SludgeHammer S-1000 ATU. Remarks updated 1/29/2025. | | | | | | | | | | | |
| 01-011-57P-C4 | C4 | 6.00 | 45.50 | 103.5 | 191.63 | 2.5 | 3000 | 3,733 | D | 2/28/2011 | |
| REMARKS: AASHTO HS20 traffic rating when buried between 18" to 48" | | | | | | | | | | | |
| 01-011-57S-C4 | C4 | 6.00 | 45.50 | 103.5 | 191.63 | 2.5 | 3000 | 3,733 | | 10/31/2001 | |
| REMARKS: AASHTO HS20 traffic loading rated when buried between 18" to 48" | | | | | | | | | | | |
| 01-011-60D-C4 | C4 | 6.00 | 60.00 | 81.25 | 157 | 2.5 | 2300 | 2,752 | B | 5/29/2002 | |
| REMARKS: AASHTO HS20 traffic loading rated when buried between 18" to 48" | | | | | | | | | | | |
| 01-011-60P-C4 | C4 | 6.00 | 60.00 | 81.25 | 157 | 2.5 | 2300 | 2,752 | D | 2/28/2011 | |
| REMARKS: AASHTO HS20 traffic rating when buried between 18" to 48" | | | | | | | | | | | |
| 01-011-60S-C4 | C4 | 6.00 | 60.00 | 81.25 | 157 | 2.5 | 2300 | 2,752 | | 5/29/2002 | |
| REMARKS: AASHTO HS20 traffic loading rated when buried between 18" to 48" | | | | | | | | | | | |

# DEPARTMENT OF ENVIRONMENTAL PROTECTION

SEPTIC TANK DESIGNATED APPROVAL NUMBERS
SEPTIC TANK MANUFACTURERS
run date: 10/9/2026
Searching for: HS20

## Florida Septic,Inc.

Alachua

**Post Office Box 545**
**Hawthorne, FL 32640**

ACTIVE

| TANK NUMBER | CATEGORY | WALL THICKNESS | LIQUID DEPTH | TOP EXTERIOR WIDTH | TOP EXTERIOR LENGTH | IN-OUT DROP | EFFECTIVE GALLONS | TOTAL GALLONS (Pump Tanks) | USE | APPROVAL DATE | FAMILY |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 01-011-65D-C4 | C4 | 6.00 | 49.50 | 103.8 | 192 | 2.5 | 3300 | 4,023 | B, ATU | 10/31/2001 | |
| REMARKS: Houses Bionest BNC-1250 ATU. AASHTO HS20 traffic loading rated when buried between 18" to 48" | | | | | | | | | | | |
| 01-011-65S-C4 | C4 | 6.00 | 49.50 | 103.8 | 192 | 2.5 | 3300 | 4,023 | | 10/31/2001 | |
| REMARKS: AASHTO HS20 traffic loading rated when buried between 18" to 48" | | | | | | | | | | | |
| 01-011-69D-C4 | C4 | 6.00 | 55.75 | 104.1 | 192.5 | 2.5 | 3700 | 4,461 | B, ATU | 5/29/2002 | |
| REMARKS: Houses Bionest BNC-1500 ATU. AASHTO HS20 traffic loading rated when buried between 18" to 48" | | | | | | | | | | | |
| 01-011-69P-C4 | C4 | 6.00 | 55.75 | 104.1 | 192.5 | 2.5 | 3700 | 4,461 | D | 2/28/2011 | |
| REMARKS: ASSHTO HS20 traffic rating when buried between 18" to 48" | | | | | | | | | | | |
| 01-011-69S-C4 | C4 | 6.00 | 55.75 | 104.1 | 192.5 | 2.5 | 3700 | 4,461 | | 5/29/2002 | |
| REMARKS: AASHTO HS20 traffic loading rated when buried between 18" to 48" | | | | | | | | | | | |
| 01-011-73D-C4 | C4 | 6.00 | 64.00 | 105.1 | 193.5 | 3 | 4300 | 5,107 | | 5/29/2002 | |
| REMARKS: AASHTO HS20 traffic loading rated when buried between 18" to 48" | | | | | | | | | | | |
| 01-011-73P-C4 | C4 | 6.00 | 64.00 | 105.1 | 193.5 | 3 | 4300 | 5,107 | D | 2/28/2011 | |
| REMARKS: ASSHTO HS20 traffic rating when buried between 18" to 48" | | | | | | | | | | | |
| 01-011-73S-C4 | C4 | 6.00 | 64.00 | 105.1 | 193.5 | 3 | 4300 | 5,107 | | 5/29/2002 | |
| REMARKS: AASHTO HS20 traffic loading rated when buried between 18" to 48" | | | | | | | | | | | |
| 01-011-77D-C4 | C4 | 6.00 | 73.50 | 106 | 194.75 | 2.75 | 5000 | 5,910 | B | 5/29/2002 | |
| REMARKS: AASHTO HS20 traffic loading rated when buried between 18" to 48" | | | | | | | | | | | |
| 01-011-77P-C4 | C4 | 6.00 | 73.50 | 106 | 194.75 | 2.75 | 5000 | 5,910 | D | 2/28/2011 | |
| REMARKS: ASSHTO HS20 traffic rating when buried between 18" to 48" | | | | | | | | | | | |
| 01-011-77S-C4 | C4 | 6.00 | 73.50 | 106 | 194.75 | 2.75 | 5000 | 5,910 | B | 5/29/2002 | |
| REMARKS: AASHTO HS20 traffic loading rated when buried between 18" to 48" | | | | | | | | | | | |
| 01-011-90D-C4 | C4 | 4.00 | 43.00 | 68.13 | 131.25 | 2.5 | 1250 | 1,500 | B, GI | 7/30/2001 | |
| REMARKS: AASHTO HS20 traffic loading rated when buried between 18" to 48" with 8" lid. Approved for GI use 5/22/2020 | | | | | | | | | | | |
| 01-011-90P-C4 | C4 | 4.00 | 43.00 | 68.13 | 131.25 | 2.5 | 1250 | 1,500 | D | 2/28/2011 | |
| REMARKS: lowered pass-through hole for dosing tank; AASHTO HS20 traffic loading rated when buried between 18" to 48" | | | | | | | | | | | |
| 01-011-90S-C4 | C4 | 4.00 | 43.00 | 68.13 | 131.13 | 2.5 | 1250 | 1,500 | | 7/30/2001 | |
| REMARKS: AASHTO HS20 traffic loading rated when buried between 18" to 48" | | | | | | | | | | | |
| 01-011-92D-C4 | C4 | 6.00 | 46.00 | 72.5 | 136.13 | 2.5 | 1350 | 1,688 | B, GI | 10/31/2001 | |
| REMARKS: AASHTO HS20 traffic loading rated when buried between 18" to 48" | | | | | | | | | | | |
| 01-011-92P-C4 | C4 | 6.00 | 46.00 | 72.5 | 136.13 | 2.5 | 1350 | 1,688 | D | 2/28/2011 | |
| REMARKS: AASHTO HS20 TRAFFIC LOADING RATED WHEN BURIED BETWEEN 18" TO 48" | | | | | | | | | | | |
| 01-011-92S-C4 | C4 | 6.00 | 46.00 | 72.5 | 136.13 | 2.5 | 1350 | 1,688 | | 10/31/2001 | |
| REMARKS: AASHTO HS20 traffic loading rated when buried between 18" to 48" | | | | | | | | | | | |

# DEPARTMENT OF ENVIRONMENTAL PROTECTION

SEPTIC TANK DESIGNATED APPROVAL NUMBERS
SEPTIC TANK MANUFACTURERS
run date: 10/9/2026
Searching for: HS20

## Florida Septic,Inc.

Alachua

**Post Office Box 545**
**Hawthorne, FL 32640**

ACTIVE

| TANK NUMBER | CATEGORY | WALL THICKNESS | LIQUID DEPTH | TOP EXTERIOR WIDTH | TOP EXTERIOR LENGTH | IN-OUT DROP | EFFECTIVE GALLONS | TOTAL GALLONS (Pump Tanks) | USE | APPROVAL DATE | FAMILY |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 01-011-93S-C4 | C4 | 4.00 | 42.00 | 47.75 | 55.75 | 1 | 300 | 373 | | 12/14/2001 | |
| REMARKS: AASHTO HS20 traffic loading rated when buried between 18" to 48" | | | | | | | | | | | |
| 01-011-BM10-C4 | C4 | 6.00 | 63.00 | 82 | 158.5 | 2.5 | 2400 | 3,021 | ATU | 3/28/2012 | |
| REMARKS: Converted 02-05-2012. Houses Bio-Microbics MicroFAST 1.5 ATU (NSF 40-certified units only).. AASHTO HS20 traffic loading rated when buried between 18" to 48". | | | | | | | | | | | |
| 01-011-BM11-C4 | C4 | 6.00 | 66.00 | 106 | 194.75 | 3 | 4500 | 5,909 | ATU | 3/28/2012 | |
| REMARKS: Used to house Bio-Microbics MicroFAST 3.0F and 3.0FS ATU. AASHTO HS20 traffic loading rated when buried between 18" to 48" | | | | | | | | | | | |
| 01-011-BM12-C4 | C4 | 6.00 | 65.00 | 106 | 194.75 | 11 | 4400 | 5,913 | ATU | 3/28/2012 | |
| REMARKS: AASHTO HS20 traffic loading rated when buried between 18" to 48". Used to house Bio-Microbics MicroFAST 4.5F ATU | | | | | | | | | | | |
| 01-011-BM9-C4 | C4 | 6.00 | 53.00 | 73 | 137 | 2.5 | 1500 | 1,919 | ATU | 10/31/2001 | |
| REMARKS: Converted 01-011-27D-C4, Houses Bio-Microbics MicroFAST ATU. NSF 40-certified units: 0.5, 0.625, 0.75, 0.9. NSF 245-certified units: 0.5, 0.625, 0.75.. AASHTO HS20 traffic loading rated when buried between 18" to 48" | | | | | | | | | | | |
| 01-011-E100H-C4 | C4 | 6.00 | 53.00 | 73 | 137 | 2.5 | 1500 | 1,920 | ATU | 4/8/2021 | |
| REMARKS: Originally approved as 01-011-27S-C4, Houses the Delta EcoPod E100-N ATU (1,000 gpd). Minimum pretreatment tank effective capacity required is 1,000 gal; maximum allowed is 2,500 gal unless specified by the design engineer. The Delta EcoPod is NSF 245-certified. Lid # 223. HS20 | | | | | | | | | | | |
| 01-011-E150H-C4 | C4 | 6.00 | 60.00 | 81.25 | 157 | 2.5 | 2300 | 1,920 | ATU | 4/8/2021 | |
| REMARKS: Originally approved as 01-011-60S-C4, Houses the Delta EcoPod E150-N ATU (1,500 gpd). Minimum pretreatment tank effective capacity required is 1,500 gal; maximum allowed is 3,750 gal unless specified by the design engineer. The Delta EcoPod is NSF 245-certified. Lid #224. HS20 | | | | | | | | | | | |
| 01-011-E200H-C4 | C4 | 6.00 | 49.50 | 103.8 | 192 | 2.5 | 3300 | 4,024 | ATU | 4/8/2021 | |
| REMARKS: Originally approved as 01-011-65S-C4, Houses the Delta EcoPod E200-DCA (2,000 gpd) engineer-designed ATU. Minimum pretreatment tank effective capacity required is 2,000 gal. Lid # 225. HS20 | | | | | | | | | | | |
| 01-011-E250H-C4 | C4 | 6.00 | 55.75 | 104.1 | 192.5 | 2.5 | 3700 | 4,460 | ATU | 4/8/2021 | |
| REMARKS: Originally approved as 01-011-69S-C3, modified structural rib. Houses the Delta EcoPod E250-DCA (2,500 gpd) engineer-designed ATU. Minimum pretreatment tank effective capacity required is 2,500 gal. Lid # 225. HS20 | | | | | | | | | | | |
| 01-011-E300H-C4 | C4 | 6.00 | 64.00 | 105.1 | 193.5 | 3 | 4300 | 5,100 | ATU | 4/8/2021 | |
| REMARKS: Originally approved as 01-011-73S-C3, Houses the Delta EcoPod E300-DCA (3,000 gpd) engineer-designed ATU. Minimum pretreatment tank effective capacity required is 3,000 gal. Lid # 225. HS20 | | | | | | | | | | | |
| 01-011-E350H-C4 | C4 | 6.00 | 73.50 | 106 | 194.75 | 2.75 | 5000 | 5,900 | ATU | 4/8/2021 | |
| REMARKS: Originally approved as 01-011-77S-C3, Houses the Delta EcoPod E350-DCA (3,500 gpd) engineer-designed ATU. Minimum pretreatment tank effective capacity required is 3,500 gal. Lid # 225. HS20 | | | | | | | | | | | |
| 01-011-E400H-C4 | C4 | 6.00 | 73.50 | 106 | 194.75 | 2.75 | 5000 | 5,900 | ATU | 4/8/2021 | |
| REMARKS: Originally approved as 01-011-77S-C3, Houses the Delta EcoPod E350-DCA (3,500 gpd) engineer-designed ATU. Minimum pretreatment tank effective capacity required is 3,500 gal. Lid # 225. HS20 | | | | | | | | | | | |

# DEPARTMENT OF ENVIRONMENTAL PROTECTION

SEPTIC TANK DESIGNATED APPROVAL NUMBERS
SEPTIC TANK MANUFACTURERS
run date: 10/9/2026
Searching for: HS20

## George W.Shepard & Son, Inc.

Collier

**PO Box 202**
**Naples FL 34106**

ACTIVE

| TANK NUMBER | CATEGORY | WALL THICKNESS | LIQUID DEPTH | TOP EXTERIOR WIDTH | TOP EXTERIOR LENGTH | IN-OUT DROP | EFFECTIVE GALLONS | TOTAL GALLONS (Pump Tanks) | USE | APPROVAL DATE | FAMILY |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 11-149-21D-C4 | C4 | 6.00 | 45.00 | 66 | 123 | 2.5 | 1050 | 1,300 | B, GI | 3/6/2019 | |
| REMARKS: HS20 traffic. Slide-in baffle Formerly manufactured by Southeastern Septic approval 53-152-21D-C4 | | | | | | | | | | | |
| 11-149-21S-C4 | C4 | 6.00 | 45.00 | 66 | 123 | 2.5 | 1050 | 1,300 | B, GI | 3/6/2019 | |
| REMARKS: HS20 traffic. Formerly manufactured by Southeastern Septic approval 53-152-21S-C4 | | | | | | | | | | | |
| 11-149-22D-C4 | C4 | 6.00 | 45.00 | 66 | 143 | 2.5 | 1250 | 1,500 | B, GI | 3/6/2019 | |
| REMARKS: HS20 traffic. Slide-in baffle Formerly manufactured by Southeastern Septic approval 53-152-22D-C4 | | | | | | | | | | | |
| 11-149-22S-C4 | C4 | 6.00 | 45.00 | 66 | 143 | 2.5 | 1250 | 1,500 | B, Gi | 3/6/2019 | |
| REMARKS: HS20 traffic. Formerly manufactured by Southeastern Septic approval 53-152-22S-C4 | | | | | | | | | | | |

# DEPARTMENT OF ENVIRONMENTAL PROTECTION

SEPTIC TANK DESIGNATED APPROVAL NUMBERS
SEPTIC TANK MANUFACTURERS
run date: 10/9/2026
Searching for: HS20

## Hanson Pipe & Precast

Hillsborough

**12781 US Hwy 41 South**
**Gibsonton, FL 33534**

ACTIVE

| TANK NUMBER | CATEGORY | WALL THICKNESS | LIQUID DEPTH | TOP EXTERIOR WIDTH | TOP EXTERIOR LENGTH | IN-OUT DROP | EFFECTIVE GALLONS | TOTAL GALLONS (Pump Tanks) | USE | APPROVAL DATE | FAMILY |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 29-139-01D-C4 | C4 | 8.00 | 58.68 | 115 | 187 | | 4300 | | | 11/28/2007 | |

REMARKS: Rated for HS20 traffic loading.

# DEPARTMENT OF ENVIRONMENTAL PROTECTION

SEPTIC TANK DESIGNATED APPROVAL NUMBERS
SEPTIC TANK MANUFACTURERS
run date: 10/9/2026
Searching for: HS20

## Highland Tanks

**One Highland Road**
**Stoystown PA 15563**

Active

| TANK NUMBER | CATEGORY | WALL THICKNESS | LIQUID DEPTH | TOP EXTERIOR WIDTH | TOP EXTERIOR LENGTH | IN-OUT DROP | EFFECTIVE GALLONS | TOTAL GALLONS (Pump Tanks) | USE | APPROVAL DATE | FAMILY |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 70-151-01102-C4 | C4 | 0.18 | 42.00 | 64 | 84 | 6 | 800 | 1,169 | GI | 3/12/2021 | |
| REMARKS: coated steel; 2 COMPARTMENTS - Highland Model No. PGI-800 FL; up to 120" burial; HS20 rated with 52"-112" of fill and 8" reinforced concrete slab | | | | | | | | | | | |
| 70-151-01302-C4 | C4 | 0.18 | 46.00 | 64 | 94 | 6 | 1000 | 1,309 | GI | 3/12/2021 | |
| REMARKS: coated steel; 2 COMPARTMENTS - Highland Model No. PGI-1000 FL; up to 120" burial; HS20 rated with 52"-112" of fill and 8" reinforced concrete slab | | | | | | | | | | | |
| 70-151-01802-C4 | C4 | 0.18 | 49.00 | 64 | 132 | 5 | 1500 | 1,838 | GI | 3/12/2021 | |
| REMARKS: coated steel; 2 COMPARTMENTS - Highland Model No. PGI-1500 FL; up to 120" burial; HS20 rated with 52"-112" of fill and 8" reinforced concrete slab | | | | | | | | | | | |
| 70-151-02602-C4 | C4 | 0.18 | 48.00 | 64 | 180 | 6 | 2000 | 2,506 | GI | 3/12/2021 | |
| REMARKS: coated steel; 2 COMPARTMENTS - Highland Model No. PGI-2000 FL; up to 60" burial; HS20 rated with 52" of fill and 8" reinforced concrete slab | | | | | | | | | | | |
| 70-151-026B2-C4 | C4 | 0.25 | 48.00 | 64 | 180 | 6 | 2000 | 2,506 | GI | 3/12/2021 | |
| REMARKS: coated steel; 2 COMPARTMENTS - Highland Model No. PGI-2000 FL; up to 120" burial; HS20 rated with 52"-112" of fill and 8" reinforced concrete slab | | | | | | | | | | | |
| 70-151-F012D1-C | C4 | 0.18 | 52.00 | 64 | 104 | 3 | 1250 | 1,400 | GI, B | 9/19/2016 | |
| REMARKS: coated steel; 1 Compartment - Highland Model PGI-1250-FL; up to 120" burial; HS20 rated with 52"-112" of fill and 8" reinforced concrete slab | | | | | | | | | | | |
| 70-151-F025D2-C | C4 | 0.25 | 51.00 | 64 | 212 | 3 | 2500 | 2,900 | GI | 9/19/2016 | |
| REMARKS: coated steel; 2 Compartments - Highland Model PGI-2500-FL 2; up to 120" burial; HS20 rated with 52"-112" of fill and 8" reinforced concrete slab | | | | | | | | | | | |
| 70-151-F025H2-C | C4 | 0.18 | 51.00 | 64 | 212 | 3 | 2500 | 2,900 | GI | 9/19/2016 | |
| REMARKS: coated steel; 2 Compartments - Highland Model PGI-2500-FL; up to 60" burial; HS20 rated with 52" of fill and 8" reinforced concrete slab | | | | | | | | | | | |
| 70-151-F030D3-C | C4 | 0.25 | 51.00 | 64 | 252 | 3 | 3000 | 3,500 | GI | 9/19/2016 | |
| REMARKS: coated steel; 3 Compartments - Highland Model PGI-3000-FL; up to 120" burial; HS20 rated with at least 52" of fill and 8" reinforced concrete slab | | | | | | | | | | | |
| 70-151-H040D4-C | C4 | 0.25 | 57.00 | 72 | 268 | 3 | 4000 | 4,700 | GI | 9/19/2016 | |
| REMARKS: coated steel; 4 Compartments - Highland Model PGI-4000-FL; up to 120" burial; HS20 rated with at least 52" of fill and 8" reinforced concrete slab | | | | | | | | | | | |
| 70-151-K050D4-C | C4 | 0.25 | 69.00 | 84 | 238 | 3 | 5000 | 5,700 | GI | 9/19/2016 | |
| REMARKS: coated steel; 4 Compartments - Highland Model PGI-5000-FL; up to 120" burial; HS20 rated with at least 52" of fill and 8" reinforced concrete slab | | | | | | | | | | | |
| 70-151-K060D5-C | C4 | 0.31 | 69.00 | 84 | 285 | 3 | 6000 | 6,800 | GI | 9/19/2016 | |
| REMARKS: coated steel; 5 Compartments - Highland Model PGI-6000-FL 2; up to 120" burial; HS20 rated with 52"-112" of fill and 8" reinforced concrete slab | | | | | | | | | | | |
| 70-151-K060H5-C | C4 | 0.25 | 69.00 | 84 | 285 | 3 | 6000 | 6,800 | GI | 9/19/2016 | |
| REMARKS: coated steel; 5 Compartments - Highland Model PGI-6000-FL; up to 60" burial; HS20 rated with 52" of fill and 8" reinforced concrete slab | | | | | | | | | | | |
| 70-151-K062D5-C | C4 | 0.31 | 70.00 | 84 | 286 | 3 | 6250 | 6,850 | GI | 4/15/2016 | 1 |
| REMARKS: coated steel; 5 Compartments - Highland Model PGI-6250-FL 120" burial; HS20 rated with at least 18" of fill and 8" reinforced concrete slab | | | | | | | | | | | |
| 70-151-K062H5-C | C4 | 0.25 | 70.00 | 84 | 286 | 3 | 6250 | 6,850 | GI | 4/15/2016 | 2 |
| REMARKS: coated steel; 5 Compartments - Highland Model PGI-6250-FL 60" burial; HS20 rated with at least 18" of fill and 8" reinforced concrete slab | | | | | | | | | | | |
| 70-151-K075D6-C | C4 | 0.31 | 69.00 | 84 | 357 | 3 | 7500 | 8,500 | GI | 9/19/2016 | |
| REMARKS: coated steel; 6 Compartments - Highland Model PGI-7500-FL; up to 120" burial; HS20 rated with 52"-112" of fill and 8" reinforced concrete slab | | | | | | | | | | | |

# Highland Tanks

**One Highland Road**
**Stoystown PA 15563**

Active

| TANK NUMBER | CATEGORY | WALL THICKNESS | LIQUID DEPTH | TOP EXTERIOR WIDTH | TOP EXTERIOR LENGTH | IN-OUT DROP | EFFECTIVE GALLONS | TOTAL GALLONS (Pump Tanks) | USE | APPROVAL DATE | FAMILY |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 70-151-K100D8-C | C4 | 0.38 | 68.00 | 84 | 484 | 5 | 10000 | 11,600 | GI | 9/19/2016 | |
| REMARKS: coated steel; 8 Compartments - Highland Model PGI-10000-FL 2; up to 120" burial; HS20 rated with 52"-112" of fill and 8" reinforced concrete slab | | | | | | | | | | | |
| 70-151-K100H8-C | C4 | 0.31 | 68.00 | 84 | 484 | 5 | 10000 | 11,600 | GI | 9/19/2016 | |
| REMARKS: coated steel; 8 Compartments - Highland Model PGI-10000-FL; up to 60" burial; HS20 rated with 52" of fill and 8" reinforced concrete slab | | | | | | | | | | | |
| 70-151-K120D10- | C4 | 0.38 | 66.00 | 84 | 600 | 7 | 12000 | 14,300 | GI | 9/19/2016 | |
| REMARKS: coated steel; 10 Compartments - Highland Model PGI-12000-FL; up to 120" burial; HS20 rated with 52"-112" of fill and 8" reinforced concrete slab | | | | | | | | | | | |
| 70-151-L150D12- | C4 | 0.38 | 72.00 | 90 | 636 | 7 | 15000 | 17,500 | GI | 9/19/2016 | |
| REMARKS: coated steel; 12 Compartments - Highland Model PGI-15000-FL; up to 120" burial; HS20 rated with 52"-112" of fill and 8" reinforced concrete slab | | | | | | | | | | | |
| 70-151-L175D14- | C4 | 0.38 | 75.00 | 96 | 672 | 7 | 17500 | 21,000 | GI | 9/19/2016 | |
| REMARKS: coated steel; 14 Compartments - Highland Model PGI-17500-FL; up to 120" burial; HS20 rated with 52"-112" of fill and 8" reinforced concrete slab | | | | | | | | | | | |
| 70-151-L200D16- | C4 | 0.38 | 75.00 | 96 | 768 | 8 | 20000 | 24,000 | GI | 9/19/2016 | |
| REMARKS: coated steel; 16 Compartments - Highland Model PGI-20000-FL; up to 120" burial; HS20 rated with 52"-112" of fill and 8" reinforced concrete slab | | | | | | | | | | | |

# DEPARTMENT OF ENVIRONMENTAL PROTECTION

SEPTIC TANK DESIGNATED APPROVAL NUMBERS
SEPTIC TANK MANUFACTURERS
run date: 10/9/2026
Searching for: HS20

## Lindsay Precast, Inc., Southern Division

Alachua

**13365 Southern Precast Drive**
**Alachua FL 32615**

ACTIVE

| TANK NUMBER | CATEGORY | WALL THICKNESS | LIQUID DEPTH | TOP EXTERIOR WIDTH | TOP EXTERIOR LENGTH | IN-OUT DROP | EFFECTIVE GALLONS | TOTAL GALLONS (Pump Tanks) | USE | APPROVAL DATE | FAMILY |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 01-132-11D-C4 | C4 | 6.00 | 40.00 | 60 | 108 | | 750 | 1,007 | GI, B | 1/9/2008 | |
| REMARKS: Approved for AASHTO HS20 traffic loading; 5,500 psi concrete; slide-in baffle | | | | | | | | | | | |
| 01-132-11S-C4 | C4 | 6.00 | 40.00 | 60 | 108 | | 750 | 1,032 | GI, B | 1/9/2008 | |
| REMARKS: Approved for AASHTO HS20 traffic loading; 5,500 psi concrete | | | | | | | | | | | |
| 01-132-12D-C4 | C4 | 6.00 | 55.00 | 60 | 108 | | 1050 | 1,298 | GI, B | 1/9/2008 | |
| REMARKS: Approved for AASHTO HS20 traffic loading; 5,500 psi concrete; slide-in baffle | | | | | | | | | | | |
| 01-132-12S-C4 | C4 | 6.00 | 55.00 | 60 | 108 | | 1050 | 1,332 | GI, B | 1/9/2008 | |
| REMARKS: Approved for AASHTO HS20 traffic loading; 5,500 psi concrete | | | | | | | | | | | |
| 01-132-13D-C4 | C4 | 6.00 | 40.00 | 72 | 138 | | 1250 | 1,663 | GI, B | 1/9/2008 | |
| REMARKS: Approved for AASHTO HS20 traffic loading; 5,500 psi concrete; slide-in baffle | | | | | | | | | | | |
| 01-132-13S-C4 | C4 | 6.00 | 40.00 | 72 | 138 | | 1250 | 1,694 | GI, B | 1/9/2008 | |
| REMARKS: Approved for AASHTO HS20 traffic loading with 1 ft minimum soil cover; 5,500 psi concrete | | | | | | | | | | | |
| 01-132-14D-C4 | C4 | 6.00 | 40.00 | 84 | 120 | 2.5 | 1250 | 1,700 | GI, B | 8/1/2013 | |
| REMARKS: Approved for AASHTO HS20 traffic loading with 1 ft minimum soil cover; 5,500 psi concrete; slide-in baffle | | | | | | | | | | | |
| 01-132-14S-C4 | C4 | 6.00 | 40.00 | 84 | 120 | 2.5 | 1250 | 1,742 | GI, B | 8/1/2013 | 2 |
| REMARKS: Approved for AASHTO HS20 traffic loading with 1 ft minimum soil cover; 5,500 psi concrete | | | | | | | | | | | |
| 01-132-15D-C4 | C4 | 6.00 | 46.00 | 84 | 120 | | 1500 | 1,901 | GI, B | 1/9/2008 | |
| REMARKS: Approved for AASHTO HS20 traffic loading with 1 ft minimum soil cover; 5,500 psi concrete; slide-in baffle | | | | | | | | | | | |
| 01-132-15S-C4 | C4 | 6.00 | 46.00 | 84 | 120 | | 1500 | 1,944 | B | 1/9/2008 | |
| REMARKS: Approved for AASHTO HS20 traffic loading with 1 ft minimum soil cover; 5,500 psi concrete | | | | | | | | | | | |
| 01-132-20D-C4 | C4 | 6.00 | 61.50 | 84 | 120 | | 2000 | 2,408 | B | 1/9/2008 | |
| REMARKS: Approved for AASHTO HS20 traffic loading with 1 ft minimum soil cover; 5,500 psi concrete; slide-in baffle | | | | | | | | | | | |
| 01-132-20S-C4 | C4 | 6.00 | 61.50 | 84 | 120 | | 2000 | 2,466 | B | 1/9/2008 | |
| REMARKS: Approved for AASHTO HS20 traffic loading with 1 ft minimum soil cover; 5,500 psi concrete | | | | | | | | | | | |
| 01-132-25S-C4 | C4 | 6.00 | 81.00 | 120 | 240 | | 10000 | 11,968 | | 4/10/2009 | |
| REMARKS: Approved for AASHTO HS20 traffic loading; 5000 psi concrete; mid-seam; holding tank only | | | | | | | | | | | |
| 01-132-34D-C4 | C4 | 6.00 | 40.00 | 84 | 120 | 2.5 | 1250 | 1,700 | GI | 4/13/2016 | 2 |
| REMARKS: Approved for AASHTO HS20 traffic loading with 1 ft minimum soil cover; 5,500 psi concrete; monolithic baffle | | | | | | | | | | | |
| 01-132-35D-C4 | C4 | 6.00 | 46.00 | 84 | 120 | 2.5 | 1500 | 1,900 | GI | 4/13/2016 | 2 |
| REMARKS: Approved for AASHTO HS20 traffic loading with 1 ft minimum soil cover; 5,500 psi concrete; monolithic baffle | | | | | | | | | | | |
| 01-132-40D-C4 | C4 | 6.00 | 61.50 | 84 | 120 | 2.5 | 2000 | 2,400 | GI, B | 4/13/2016 | 2 |
| REMARKS: Approved for AASHTO HS20 traffic loading with 1 ft minimum soil cover; 5,500 psi concrete; monolithic baffle | | | | | | | | | | | |
| 01-132-44D-C4 | C4 | 6.00 | 42.00 | 84 | 120 | 2.5 | 1360 | 1,900 | GI | 4/13/2016 | 2 |
| REMARKS: Approved for AASHTO HS20 traffic loading with 1 ft minimum soil cover; 5,500 psi concrete; 4" slide-in baffle | | | | | | | | | | | |

# DEPARTMENT OF ENVIRONMENTAL PROTECTION

SEPTIC TANK DESIGNATED APPROVAL NUMBERS
SEPTIC TANK MANUFACTURERS
run date: 10/9/2026
Searching for: HS20

## Lindsay Precast, Inc., Southern Division

Alachua

**13365 Southern Precast Drive**
**Alachua FL 32615**

ACTIVE

| TANK NUMBER | CATEGORY | WALL THICKNESS | LIQUID DEPTH | TOP EXTERIOR WIDTH | TOP EXTERIOR LENGTH | IN-OUT DROP | EFFECTIVE GALLONS | TOTAL GALLONS (Pump Tanks) | USE | APPROVAL DATE | FAMILY |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 01-132-45D-C4 | C4 | 6.00 | 47.00 | 84 | 120 | 2.5 | 1500 | 2,100 | GI | 4/13/2016 | 2 |
| REMARKS: Approved for AASHTO HS20 traffic loading with 1 ft minimum soil cover; 5,500 psi concrete; 4" slide-in baffle | | | | | | | | | | | |
| 01-132-46D-C4 | C4 | 6.00 | 33.50 | 66 | 114 | 2.5 | 750 | 1,054 | GI | 5/31/2018 | |
| REMARKS: Approved for AASHTO HS20 traffic loading with 1 ft minimum soil cover; 5,500 psi concrete; monolithic baffle | | | | | | | | | | | |
| 01-132-47D-C4 | C4 | 6.00 | 46.00 | 66 | 114 | 2.5 | 1050 | 1,329 | GI | 5/31/2018 | |
| REMARKS: Approved for AASHTO HS20 traffic loading with 1 ft minimum soil cover; 5,500 psi concrete; monolithic baffle | | | | | | | | | | | |
| 01-132-48D-C4 | C4 | 6.00 | 55.50 | 66 | 114 | 2.5 | 1250 | 1,535 | GI | 5/31/2018 | |
| REMARKS: Approved for AASHTO HS20 traffic loading with 1 ft minimum soil cover; 5,500 psi concrete; monolithic baffle | | | | | | | | | | | |
| 01-132-49D-C4 | C4 | 6.00 | 65.50 | 66 | 114 | 2.5 | 1500 | 1,764 | GI | 5/31/2018 | |
| REMARKS: Approved for AASHTO HS20 traffic loading with 1 ft minimum soil cover; 5,500 psi concrete; monolithic baffle | | | | | | | | | | | |

# DEPARTMENT OF ENVIRONMENTAL PROTECTION

SEPTIC TANK DESIGNATED APPROVAL NUMBERS
SEPTIC TANK MANUFACTURERS
run date: 10/9/2026
Searching for: HS20

## Mid-State Precast, Inc.

**8037 Commercial Blvd.**
**Sebring FL 33870**

Highlands
ACTIVE

| TANK NUMBER | CATEGORY | WALL THICKNESS | LIQUID DEPTH | TOP EXTERIOR WIDTH | TOP EXTERIOR LENGTH | IN-OUT DROP | EFFECTIVE GALLONS | TOTAL GALLONS (Pump Tanks) | USE | APPROVAL DATE | FAMILY |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 28-O15-10D-C4 | C4 | 6.00 | 53.30 | | | | 1050 | | ATU | 4/22/2002 | |
| REMARKS: Houses Bionest BNC-400 ATU. HS20 traffic rated | | | | | | | | | | | |
| 28-O15-10S-C4 | C4 | 6.00 | 53.30 | | | | 1050 | | | 4/22/2002 | |
| REMARKS: HS20 traffic rated | | | | | | | | | | | |
| 28-O15-15D-C4 | C4 | 6.00 | 57.80 | 67.6 | 109.4 | | 1250 | 1,456 | | 8/24/2010 | |
| REMARKS: HS20 traffic rated; slide-in baffle | | | | | | | | | | | |
| 28-O15-15S-C4 | C4 | 6.00 | 57.80 | 67.6 | 109.4 | | 1250 | 1,483 | | 8/24/2010 | |
| REMARKS: HS20 traffic rated | | | | | | | | | | | |
| 28-O15-24D-C4 | C4 | 6.00 | 42.00 | 90 | 130 | | 1500 | | ATU | 4/22/2002 | |
| REMARKS: Without slide-in baffle, houses Bio-Microbics MicroFAST 1.5 ATU when used with 713 gallon min pretreatment tank (02/26/10) (NSF 40-certified units only). HS20 traffic rated. | | | | | | | | | | | |
| 28-O15-24S-C4 | C4 | 6.00 | 42.00 | 90 | 130 | | 1500 | | ATU | 4/22/2002 | |
| REMARKS: Houses Bio-Microbics MicroFAST 1.5 ATU when used with 713 gallon min pretreatment tank (02/26/10) (NSF 40-certified units only). HS20 traffic rated. | | | | | | | | | | | |
| 28-O15-34D-C4 | C4 | 6.00 | 56.00 | | | | 2000 | | ATU | 4/22/2002 | |
| REMARKS: Houses Bionest BNC-750 ATU. HS20 traffic rated | | | | | | | | | | | |
| 28-O15-34S-C4 | C4 | 6.00 | 56.00 | | | | 2000 | | | 4/22/2002 | |
| REMARKS: HS20 traffic rated | | | | | | | | | | | |
| 28-O15-37BD-C4 | C4 | 4.00 | 50.00 | 77 | 158 | 2 | 2000 | 2,389 | | 10/9/2026 | |
| REMARKS: HS20 traffic rated only with H20 rated lid. Dual compartment tank with monolithic baffle. Lid DEP#254 (5” thick) and Lid DEP#255 (H20 rated, 8” thick). Manufactured with six anchor points on the long wall corners with the tank bottom to attach to a 6” concrete hydrostatic slab. | | | | | | | | | | | |
| 28-O15-37D-C4 | C4 | 4.00 | 50.00 | 77 | 158 | 2 | 2000 | 2,389 | | 5/15/2026 | |
| REMARKS: HS20 traffic rated only with H20 rated lid. Dual compartment tank with monolithic baffle. Lid DEP#254 (5” thick) and Lid DEP#255 (H20 rated, 8” thick). | | | | | | | | | | | |
| 28-O15-46D-C4 | C4 | 6.00 | 70.00 | | | | 2500 | | ATU | 12/12/2000 | |
| REMARKS: Houses Bionest BNC-1000 ATU. HS20 traffic rated | | | | | | | | | | | |
| 28-O15-46S-C4 | C4 | 6.00 | 70.00 | | | | 2500 | | | 12/12/2000 | |
| REMARKS: HS20 traffic rated | | | | | | | | | | | |
| 28-O15-58D-C4 | C4 | 6.00 | 83.00 | | | | 3000 | | | 4/22/2002 | |
| REMARKS: HS20 traffic rated. Mid-seam | | | | | | | | | | | |
| 28-O15-58S-C4 | C4 | 6.00 | 83.00 | | | | 3000 | | | 4/22/2002 | |
| REMARKS: HS20 traffic rated. Can also be used as 3650 gallon pump tank. Mid-seam | | | | | | | | | | | |
| 28-O15-75D-C4 | C4 | 6.00 | 40.00 | 68 | 109.88 | 2.5 | 800 | 1,050 | B, GI | 12/16/2013 | |
| REMARKS: HS20 traffic rated. Slide-in baffle | | | | | | | | | | | |
| 28-O15-75S-C4 | C4 | 6.00 | 40.00 | 68 | 109.88 | 2.5 | 800 | 1,050 | B, GI | 12/16/2013 | |
| REMARKS: HS20 traffic rated | | | | | | | | | | | |

## DEPARTMENT OF ENVIRONMENTAL PROTECTION

SEPTIC TANK DESIGNATED APPROVAL NUMBERS
SEPTIC TANK MANUFACTURERS
run date: 10/9/2026
Searching for: HS20

# Modern Welding Company of Florida, INC.

Orange

**Post Office Box 568678**
**Orlando FL 32856-8678**

ACTIVE

| TANK NUMBER | CATEGORY | WALL THICKNESS | LIQUID DEPTH | TOP EXTERIOR WIDTH | TOP EXTERIOR LENGTH | IN-OUT DROP | EFFECTIVE GALLONS | TOTAL GALLONS (Pump Tanks) | USE | APPROVAL DATE | FAMILY |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 48-158-D011H1-C | C4 | 0.17 | 40.00 | 48 | 163 | 2.5 | 1126 | 1,250 | GI | 2/8/2018 | 1 |
| REMARKS: Coated steel; 1 Compartment - Modern Welding Drawing # 9281994; up to 60" burial; HS20 rated with minimum cover of 32", including at least 8 " of concrete. Not enough air space for septic tank use. | | | | | | | | | | | |
| 48-158-F021H2-C | C4 | 0.17 | 50.50 | 64 | 180 | 2.5 | 2100 | 2,500 | GI | 12/21/2018 | 2 |
| REMARKS: Coated steel; 2 Compartment - Modern Welding Drawing # 711991; up to 60" burial; HS20 rated with minimum cover of 27", including at least 8 " of concrete. | | | | | | | | | | | |

# DEPARTMENT OF ENVIRONMENTAL PROTECTION

SEPTIC TANK DESIGNATED APPROVAL NUMBERS
SEPTIC TANK MANUFACTURERS
run date: 10/9/2026
Searching for: HS20

## Oldcastle Precast, Inc. Orlando

Orange

**690 W Taft-Vineland Rd**
**Orlando FL 32824**

ACTIVE

| TANK NUMBER | CATEGORY | WALL THICKNESS | LIQUID DEPTH | TOP EXTERIOR WIDTH | TOP EXTERIOR LENGTH | IN-OUT DROP | EFFECTIVE GALLONS | TOTAL GALLONS (Pump Tanks) | USE | APPROVAL DATE | FAMILY |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 48-106-075D-C4 | C4 | 5.00 | 51.00 | 58 | 88 | 2.5 | 750 | 900 | GI | 2/20/2017 | |
| REMARKS: slide-in baffle, flow-through hole invert 13.5"; not for septic tank use; 6,000 psi concrete; HS20, 0-4 ft of cover; drawing 374-GT750-48x78-DOH | | | | | | | | | | | |
| 48-106-075S-C4 | C4 | 5.00 | 51.00 | 58 | 88 | 2.5 | 750 | 950 | B,GI | 2/20/2017 | |
| REMARKS: 6,000 psi concrete; HS20, 0-4 ft of cover; drawing 374-GT750-48x78-DOH | | | | | | | | | | | |
| 48-106-076D-C4 | C4 | 6.00 | 40.00 | 60 | 108 | 2.5 | 750 | 950 | GI | 2/20/2017 | |
| REMARKS: slide-in baffle, flow-through hole invert 16.5"; not for septic tank use; 5,500 psi concrete; HS20, 0-4 ft of cover; drawing 374-GT750-48x96-DOH | | | | | | | | | | | |
| 48-106-076S-C4 | C4 | 6.00 | 40.00 | 60 | 108 | 2.5 | 750 | 1,000 | B,GI | 2/20/2017 | |
| REMARKS: 5,500 psi concrete; HS20, 0-4 ft of cover; drawing 374-GT750-48x96-DOH | | | | | | | | | | | |
| 48-106-100D-C4 | C4 | 6.00 | 48.00 | 72 | 96 | 2.5 | 1000 | 1,200 | GI | 2/20/2017 | |
| REMARKS: slide-in baffle, flow-through hole invert 15.5"; not for septic tank use; 6,000 psi concrete; HS20, 0-4 ft of cover; drawing 374-GT750-60x84-DOH | | | | | | | | | | | |
| 48-106-100S-C4 | C4 | 6.00 | 48.00 | 72 | 96 | 2.5 | 1000 | 1,250 | B,GI | 2/20/2017 | |
| REMARKS: 6,000 psi concrete; HS20, 0-4 ft of cover; drawing 374-GT750-60x84-DOH | | | | | | | | | | | |
| 48-106-125D-C4 | C4 | 6.00 | 40.00 | 72 | 138 | 2.5 | 1250 | 1,650 | GI | 2/20/2017 | |
| REMARKS: slide-in baffle, flow-through hole invert 13.5"; not for septic tank use; 5,500 psi concrete; HS20, 0-4 ft of cover; drawing 374-GT750-60x126-DOH_B | | | | | | | | | | | |
| 48-106-125S-C4 | C4 | 6.00 | 40.00 | 72 | 138 | 2.5 | 1250 | 1,700 | B,GI | 2/20/2017 | |
| REMARKS: 5,500 psi concrete; HS20, 0-4 ft of cover; drawing 374-GT750-60x126-DOH_B | | | | | | | | | | | |
| 48-106-126D-C4 | C4 | 6.00 | 44.00 | 84 | 108 | 2.5 | 1250 | 1,550 | GI | 2/20/2017 | |
| REMARKS: slide-in baffle, flow-through hole invert 14.5"; not for septic tank use; 6,000 psi concrete; HS20, 0-4 ft of cover; drawing 374-GT750-72x96-DOH | | | | | | | | | | | |
| 48-106-126S-C4 | C4 | 6.00 | 44.00 | 84 | 108 | 2.5 | 1250 | 1,600 | B,GI | 2/20/2017 | |
| REMARKS: 6,000 psi concrete; HS20, 0-4 ft of cover; drawing 374-GT750-72x96-DOH | | | | | | | | | | | |
| 48-106-175D-C4 | C4 | 6.00 | 40.00 | 84 | 156 | 2.5 | 1750 | 2,300 | GI | 2/20/2017 | |
| REMARKS: slide-in baffle, flow-through hole invert 11"; not for septic tank use; 5,500 psi concrete; HS20, 0-4 ft of cover | | | | | | | | | | | |
| 48-106-175S-C4 | C4 | 6.00 | 40.00 | 84 | 156 | 2.5 | 1750 | 2,350 | B,GI | 2/20/2017 | |
| REMARKS: 5,500 psi concrete; HS20, 0-4 ft of cover | | | | | | | | | | | |

# DEPARTMENT OF ENVIRONMENTAL PROTECTION

SEPTIC TANK DESIGNATED APPROVAL NUMBERS
SEPTIC TANK MANUFACTURERS
run date: 10/9/2026
Searching for: HS20

## Rick's Pre Fab

Dade

**8450 SW 43 Terrace**
**Miami FL 33155**

ACTIVE

| TANK NUMBER | CATEGORY | WALL THICKNESS | LIQUID DEPTH | TOP EXTERIOR WIDTH | TOP EXTERIOR LENGTH | IN-OUT DROP | EFFECTIVE GALLONS | TOTAL GALLONS (Pump Tanks) | USE | APPROVAL DATE | FAMILY |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 13-045-31D-C4 | C4 | 6.00 | 51.00 | 66 | 96 | 2.5 | 900 | | B, GI | 9/22/2009 | |
| REMARKS: HS20 traffic rating | | | | | | | | | | | |
| 13-045-31S-C4 | C4 | 6.00 | 51.00 | 66 | 96 | 2.5 | 900 | | B, GI, | 9/22/2009 | |
| REMARKS: HS20 traffic rating. Also houses Bio-Microbics MicroFAST ATU. NSF 40-certified units: MicroFAST 0.5 (333 gal min. settling tank required); NSF 245 units: MicroFAST 0.5, (475 to 750 gal. settling tank required); RetroFAST 0.25 and 0.375 as Alternative Drainfield Repair. | | | | | | | | | | | |
| 13-045-32D-C4 | C4 | 6.00 | 51.00 | 66 | 110 | 2.5 | 1050 | | B, GI | 9/22/2009 | |
| REMARKS: HS20 traffic rating | | | | | | | | | | | |
| 13-045-32S-C4 | C4 | 6.00 | 51.00 | 66 | 110 | 2.5 | 1050 | | B, GI, | 9/22/2009 | |
| REMARKS: HS20 traffic rating. Also houses Bio-Microbics MicroFAST ATU. NSF 40-certified units: MicroFAST 0.5 (333 gal min. settling tank required); MicroFAST 0.625, 0.75 (356 gal min. settling tank required); MicroFAST 0.9 (475 gal min. settling tank required); NSF 245-certified units: MicroFAST 0.5, 0.625, 0.75 (475 to 750 gal. settling tank required). Houses HS 1.0 with 500 gallon min. pretreatment tank. Houses RetroFAST 0.25 and 0.375 as Alternative Drainfield Repair. | | | | | | | | | | | |
| 13-045-33D-C4 | C4 | 6.00 | 51.00 | 74 | 108 | 2.5 | 1200 | | B, GI | 9/22/2009 | |
| REMARKS: HS20 traffic rating | | | | | | | | | | | |
| 13-045-33S-C4 | C4 | 6.00 | 51.00 | 74 | 108 | 2.5 | 1200 | | B, GI, | 9/22/2009 | |
| REMARKS: HS20 traffic rating. Also houses RetroFAST 0.25, 0.375 as Alternative Drainfield Repair. Houses Bio-Microbics MicroFAST ATU. NSF 40-certified units: MicroFAST 0.5 (333 gal min. settling tank required); MicroFAST 0.625, 0.75 (356 gal min. settling tank required); MicroFAST 0.9 (475 gal min. settling tank required) Microfast 1.5 (713 gal. min settling tank required). NSF 245 units: MicroFAST 0.5, 0.625, 0.75 (475 to 750 gal. settling tank required); MicroFAST 0.9 (689 to 1088 gal min. settling tank required). | | | | | | | | | | | |
| 13-045-34D-C4 | C4 | 6.00 | 51.00 | 77 | 126 | 2.5 | 1500 | | B, GI | 9/22/2009 | |
| REMARKS: HS20 traffic rating | | | | | | | | | | | |
| 13-045-34S-C4 | C4 | 6.00 | 51.00 | 77 | 126 | 2.5 | 1500 | | B, ATU | 9/22/2009 | |
| REMARKS: HS20 traffic rating. Houses Bio-Microbics MicroFAST ATU. NSF 40-certified units: MicroFAST 0.5 (333 gal min. settling tank required); MicroFAST 0.625, 0.75 (356 gal min. settling tank required); MicroFAST 0.9 (475 gal min. settling tank required) Microfast 1.5 (713 gal. min settling tank required); NSF 245 units: MicroFAST 0.5, 0.625, 0.75 (475 to 750 gal. settling tank required); MicroFAST 0.9 (689 to 1088 gal. settling tank required). Can house HS 1.0. | | | | | | | | | | | |
| 13-045-35S-C4 | C4 | 6.00 | 42.00 | 51 | 59 | 2.5 | 300 | | D | 9/22/2009 | |
| REMARKS: HS20 traffic rating. | | | | | | | | | | | |

# DEPARTMENT OF ENVIRONMENTAL PROTECTION

SEPTIC TANK DESIGNATED APPROVAL NUMBERS
SEPTIC TANK MANUFACTURERS
run date: 10/9/2026
Searching for: HS20

## Standard Precast

Duval

**PO Box 61839**
**Jacksonville FL 32236**

ACTIVE

| TANK NUMBER | CATEGORY | WALL THICKNESS | LIQUID DEPTH | TOP EXTERIOR WIDTH | TOP EXTERIOR LENGTH | IN-OUT DROP | EFFECTIVE GALLONS | TOTAL GALLONS (Pump Tanks) | USE | APPROVAL DATE | FAMILY |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 16-145-06D-C4 | C4 | 6.00 | 62.00 | 96 | 152 | | 3021 | | | 4/15/2009 | |

REMARKS: 2700 gallon septic tank for fire station #28----approved for HS20 traffic loading

# DEPARTMENT OF ENVIRONMENTAL PROTECTION

SEPTIC TANK DESIGNATED APPROVAL NUMBERS
SEPTIC TANK MANUFACTURERS
run date: 10/9/2026
Searching for: HS20

## U.S. Concrete Products Corporation

Broward

**1888 N.W. 21st Street**
**Pompano Beach, FL 33069**

Active

| TANK NUMBER | CATEGORY | WALL THICKNESS | LIQUID DEPTH | TOP EXTERIOR WIDTH | TOP EXTERIOR LENGTH | IN-OUT DROP | EFFECTIVE GALLONS | TOTAL GALLONS (Pump Tanks) | USE | APPROVAL DATE | FAMILY |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 06-096-07D-C4 | C4 | 6.00 | 54.00 | 60 | 84 | 2.5 | 750 | 904 | GI | 6/4/2019 | |
| REMARKS: HS20 traffic loading rated when buried at least 18" below grade and used with 8" traffic lid | | | | | | | | | | | |
| 06-096-12D-C4 | C4 | 6.00 | 42.00 | 68 | 144 | 2.5 | 1250 | 1,605 | GI | 6/4/2019 | |
| REMARKS: HS20 traffic loading rated when buried at least 18" below grade and used with 8" traffic lid | | | | | | | | | | | |

# DEPARTMENT OF ENVIRONMENTAL PROTECTION

SEPTIC TANK DESIGNATED APPROVAL NUMBERS
SEPTIC TANK MANUFACTURERS
run date: 10/9/2026
Searching for: HS20

## United Concrete Products, LLC (Medley)

Dade

**8351 N.W. 93rd Street**
**Medley, FL 33166**

ACTIVE

| TANK NUMBER | CATEGORY | WALL THICKNESS | LIQUID DEPTH | TOP EXTERIOR WIDTH | TOP EXTERIOR LENGTH | IN-OUT DROP | EFFECTIVE GALLONS | TOTAL GALLONS (Pump Tanks) | USE | APPROVAL DATE | FAMILY |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 13-094-13S-C3 | C3 | 8.00 | 63.00 | 24 | 192 | | 1250 | 1,496 | | 6/19/2007 | |
| REMARKS: grease trap-8" wall thickness-Rated for HS20 traffic loading | | | | | | | | | | | |
| 13-094-25D-C4 | C4 | 6.00 | 66.50 | 60 | 108 | 2.5 | 1250 | 1,500 | B, GI | 6/26/2013 | |
| REMARKS: secondary pour baffle; HS20 traffic rated with 12" minimum cover; engineer of record for installation to verify design assumptions; water stop requires water-tightness test after field installation per 64E-6.013(10)(d) | | | | | | | | | | | |
| 13-094-51D-C4 | C4 | 6.00 | 61.50 | 54 | 84 | 2.5 | 750 | 900 | B, GI | 12/18/2015 | |
| REMARKS: secondary pour baffle; HS20 traffic rated with 12" minimum cover; engineer of record for installation to verify design assumptions; water stop requires water-tightness test after field installation per 64E-6.013(10)(d) | | | | | | | | | | | |
| 13-094-51S-C4 | C4 | 6.00 | 61.50 | 54 | 84 | 2.5 | 750 | 900 | B, GI | 12/18/2015 | |
| REMARKS: HS20 traffic rated with 12" minimum cover; engineer of record for installation to verify design assumptions; water stop requires water-tightness test after field installation per 64E-6.013(10)(d) | | | | | | | | | | | |
| 13-094-52D-C4 | C4 | 6.00 | 61.50 | 54 | 84 | 2.5 | 900 | 1,100 | B, GI | 12/18/2015 | |
| REMARKS: monolithic baffle; HS20 traffic rated with 12" minimum cover; engineer of record for installation to verify design assumptions; water stop requires water-tightness test after field installation per 64E-6.013(10)(d) | | | | | | | | | | | |
| 13-094-52S-C4 | C4 | 6.00 | 61.50 | 54 | 84 | 2.5 | 900 | 1,100 | B, GI | 12/18/2015 | |
| REMARKS: HS20 traffic rated with 12" minimum cover; engineer of record for installation to verify design assumptions; water stop requires water-tightness test after field installation per 64E-6.013(10)(d) | | | | | | | | | | | |
| 13-094-53D-C4 | C4 | 6.00 | 55.50 | 60 | 108 | 2.5 | 1050 | 1,300 | B, GI | 12/18/2015 | |
| REMARKS: secondary pour baffle; HS20 traffic rated with 12" minimum cover; engineer of record for installation to verify design assumptions; water stop requires water-tightness test after field installation per 64E-6.013(10)(d) | | | | | | | | | | | |
| 13-094-53S-C4 | C4 | 6.00 | 55.50 | 60 | 108 | 2.5 | 1050 | 1,300 | B, GI | 12/18/2015 | |
| REMARKS: HS20 traffic rated with 12" minimum cover; engineer of record for installation to verify design assumptions; wwater stop requires water-tightness test after field installation per 64E-6.013(10)(d) | | | | | | | | | | | |
| 13-094-54D-C4 | C4 | 6.00 | 64.50 | 60 | 108 | 2.5 | 1200 | 1,500 | B, GI | 12/18/2015 | |
| REMARKS: secondary pour baffle; HS20 traffic rated with 12" minimum cover; engineer of record for installation to verify design assumptions; water stop requires water-tightness test after field installation per 64E-6.013(10)(d) | | | | | | | | | | | |
| 13-094-54S-C4 | C4 | 6.00 | 64.50 | 60 | 108 | 2.5 | 1200 | 1,500 | B, GI | 12/18/2015 | |
| REMARKS: HS20 traffic rated; water stop requires water-tightness test after field installation per 64E-6.013(10)(d) | | | | | | | | | | | |
| 13-094-55D-C4 | C4 | 6.00 | 66.50 | 60 | 108 | 2.5 | 1250 | 1,500 | B, GI | 12/18/2015 | |
| REMARKS: secondary pour baffle; HS20 traffic rated with 12" minimum cover; engineer of record for installation to verify design assumptions; water stop requires water-tightness test after field installation per 64E-6.013(10)(d) | | | | | | | | | | | |
| 13-094-55S-C4 | C4 | 6.00 | 67.50 | 60 | 108 | 2.5 | 1250 | 1,500 | B, GI | 12/18/2015 | |
| REMARKS: HS20 traffic rated with 12" minimum cover; engineer of record for installation to verify design assumptions; water stop requires water-tightness test after field installation per 64E-6.013(10)(d) | | | | | | | | | | | |
| 13-094-56D-C4 | C4 | 6.00 | 72.50 | 60 | 108 | 2.5 | 1350 | 1,600 | B, GI | 12/18/2015 | |
| REMARKS: secondary pour baffle; HS20 traffic rated with 12" minimum cover; engineer of record for installation to verify design assumptions; water stop requires water-tightness test after field installation per 64E-6.013(10)(d) | | | | | | | | | | | |
| 13-094-56S-C4 | C4 | 6.00 | 72.50 | 60 | 108 | 2.5 | 1350 | 1,600 | B | 12/18/2015 | |
| REMARKS: HS20 traffic rated with 12" minimum cover; engineer of record for installation to verify design assumptions; water stop requires water-tightness test after field installation per 64E-6.013(10)(d) | | | | | | | | | | | |

# DEPARTMENT OF ENVIRONMENTAL PROTECTION

SEPTIC TANK DESIGNATED APPROVAL NUMBERS
SEPTIC TANK MANUFACTURERS
run date: 10/9/2026
Searching for: HS20

## United Concrete Products, LLC (Medley)

Dade

**8351 N.W. 93rd Street**
**Medley, FL 33166**

ACTIVE

| TANK NUMBER | CATEGORY | WALL THICKNESS | LIQUID DEPTH | TOP EXTERIOR WIDTH | TOP EXTERIOR LENGTH | IN-OUT DROP | EFFECTIVE GALLONS | TOTAL GALLONS (Pump Tanks) | USE | APPROVAL DATE | FAMILY |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 13-094-57D-C4 | C4 | 6.00 | 53.50 | 84 | 108 | 2.5 | 1500 | 1,900 | B, GI | 12/18/2015 | |
| REMARKS: secondary pour baffle; HS20 traffic rated with 12" minimum cover; engineer of record for installation to verify design assumptions; water stop requires water-tightness test after field installation per 64E-6.013(10)(d) | | | | | | | | | | | |
| 13-094-57S-C4 | C4 | 6.00 | 53.50 | 84 | 108 | 2.5 | 1500 | 1,900 | B | 12/18/2015 | |
| REMARKS: HS20 traffic rated with 12" minimum cover; engineer of record for installation to verify design assumptions; water stop requires water-tightness test after field installation per 64E-6.013(10)(d) | | | | | | | | | | | |
| 13-094-58D-C4 | C4 | 6.00 | 72.50 | 84 | 108 | 2.5 | 2000 | 2,400 | B | 12/18/2015 | |
| REMARKS: secondary pour baffle; HS20 traffic rated with 12" minimum cover; engineer of record for installation to verify design assumptions; water stop requires water-tightness test after field installation per 64E-6.013(10)(d) | | | | | | | | | | | |
| 13-094-58S-C4 | C4 | 6.00 | 72.50 | 84 | 108 | 2.5 | 2000 | 2,400 | B | 12/18/2015 | |
| REMARKS: HS20 traffic rated with 12" minimum cover; engineer of record for installation to verify design assumptions; water stop requires water-tightness test after field installation per 64E-6.013(10)(d) | | | | | | | | | | | |
| 13-094-59D-C4 | C4 | 6.00 | 58.50 | 84 | 156 | 2.5 | 2500 | 3,100 | B | 12/18/2015 | |
| REMARKS: secondary pour baffle; HS20 traffic rated with 12" minimum cover; engineer of record for installation to verify design assumptions; water stop requires water-tightness test after field installation per 64E-6.013(10)(d) | | | | | | | | | | | |
| 13-094-59S-C4 | C4 | 6.00 | 58.50 | 84 | 156 | 2.5 | 2500 | 3,100 | B | 12/18/2015 | |
| REMARKS: HS20 traffic rated with 12" minimum cover; engineer of record for installation to verify design assumptions; water stop requires water-tightness test after field installation per 64E-6.013(10)(d) | | | | | | | | | | | |
| 13-094-60D-C4 | C4 | 6.00 | 69.50 | 84 | 156 | 2.5 | 3000 | 3,600 | B | 12/18/2015 | |
| REMARKS: secondary pour baffle; HS20 traffic rated with 12" minimum cover; engineer of record for installation to verify design assumptions; water stop requires water-tightness test after field installation per 64E-6.013(10)(d) | | | | | | | | | | | |
| 13-094-60S-C4 | C4 | 6.00 | 69.50 | 84 | 156 | 2.5 | 3000 | 3,600 | B | 12/18/2015 | |
| REMARKS: HS20 traffic rated with 12" minimum cover; engineer of record for installation to verify design assumptions; water stop requires water-tightness test after field installation per 64E-6.013(10)(d) | | | | | | | | | | | |
| 13-094-61D-C4 | C4 | 6.00 | 61.50 | 54 | 84 | 2.5 | 750 | 900 | B, GI | 12/18/2015 | |
| REMARKS: secondary pour baffle; HS20 traffic rated with 12" minimum cover; engineer of record for installation to verify design assumptions | | | | | | | | | | | |
| 13-094-61S-C4 | C4 | 6.00 | 61.50 | 54 | 84 | 2.5 | 750 | 900 | B, GI | 12/18/2015 | |
| REMARKS: HS20 traffic rated with 12" minimum cover; engineer of record for installation to verify design assumptions | | | | | | | | | | | |
| 13-094-62D-C4 | C4 | 6.00 | 61.50 | 54 | 84 | 2.5 | 900 | 1,100 | B, GI | 12/18/2015 | |
| REMARKS: secondary pour baffle; HS20 traffic rated with 12" minimum cover; engineer of record for installation to verify design assumptions | | | | | | | | | | | |
| 13-094-62S-C4 | C4 | 6.00 | 61.50 | 54 | 84 | 2.5 | 900 | 1,100 | B, GI | 12/18/2015 | |
| REMARKS: HS20 traffic rated with 12" minimum cover; engineer of record for installation to verify design assumptions | | | | | | | | | | | |
| 13-094-63D-C4 | C4 | 6.00 | 55.50 | 60 | 108 | 2.5 | 1050 | 1,300 | B, GI | 12/18/2015 | |
| REMARKS: secondary pour baffle; HS20 traffic rated with 12" minimum cover; engineer of record for installation to verify design assumptions | | | | | | | | | | | |
| 13-094-63S-C4 | C4 | 6.00 | 55.50 | 60 | 108 | 2.5 | 1050 | 1,300 | B, GI | 12/18/2015 | |
| REMARKS: HS20 traffic rated with 12" minimum cover; engineer of record for installation to verify design assumptions | | | | | | | | | | | |
| 13-094-64D-C4 | C4 | 6.00 | 64.50 | 60 | 108 | 2.5 | 1200 | 1,500 | B, GI | 12/18/2015 | |
| REMARKS: secondary pour baffle; HS20 traffic rated with 12" minimum cover; engineer of record for installation to verify design assumptions | | | | | | | | | | | |

# DEPARTMENT OF ENVIRONMENTAL PROTECTION

SEPTIC TANK DESIGNATED APPROVAL NUMBERS
SEPTIC TANK MANUFACTURERS
run date: 10/9/2026
Searching for: HS20

## United Concrete Products, LLC (Medley)

Dade

**8351 N.W. 93rd Street**
**Medley, FL 33166**

ACTIVE

| TANK NUMBER | CATEGORY | WALL THICKNESS | LIQUID DEPTH | TOP EXTERIOR WIDTH | TOP EXTERIOR LENGTH | IN-OUT DROP | EFFECTIVE GALLONS | TOTAL GALLONS (Pump Tanks) | USE | APPROVAL DATE | FAMILY |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 13-094-64S-C4 | C4 | 6.00 | 64.50 | 60 | 108 | 2.5 | 1200 | 1,500 | B, GI | 12/18/2015 | |
| REMARKS: HS20 traffic rated with 12" minimum cover; engineer of record for installation to verify design assumptions | | | | | | | | | | | |
| 13-094-65D-C4 | C4 | 6.00 | 67.50 | 60 | 108 | 2.5 | 1250 | 1,500 | B, GI | 12/18/2015 | |
| REMARKS: secondary pour baffle; HS20 traffic rated with 12" minimum cover; engineer of record for installation to verify design assumptions | | | | | | | | | | | |
| 13-094-65S-C4 | C4 | 6.00 | 67.50 | 60 | 108 | 2.5 | 1250 | 1,500 | B, GI | 12/18/2015 | |
| REMARKS: HS20 traffic rated with 12" minimum cover; engineer of record for installation to verify design assumptions | | | | | | | | | | | |
| 13-094-66D-C4 | C4 | 6.00 | 72.50 | 60 | 108 | 2.5 | 1350 | 1,600 | B, GI | 12/18/2015 | |
| REMARKS: secondary pour baffle; HS20 traffic rated with 12" minimum cover; engineer of record for installation to verify design assumptions | | | | | | | | | | | |
| 13-094-66S-C4 | C4 | 6.00 | 72.50 | 60 | 108 | 2.5 | 1350 | 1,600 | B, GI | 12/18/2015 | |
| REMARKS: HS20 traffic rated with 12" minimum cover; engineer of record for installation to verify design assumptions | | | | | | | | | | | |

# DEPARTMENT OF ENVIRONMENTAL PROTECTION

SEPTIC TANK DESIGNATED APPROVAL NUMBERS
SEPTIC TANK MANUFACTURERS
run date: 10/9/2026
Searching for: HS20

## WPR, INC.

**4175 Briarglen Rd**
**Milton, FL 32583**

Santa Rosa
ACTIVE

| TANK NUMBER | CATEGORY | WALL THICKNESS | LIQUID DEPTH | TOP EXTERIOR WIDTH | TOP EXTERIOR LENGTH | IN-OUT DROP | EFFECTIVE GALLONS | TOTAL GALLONS (Pump Tanks) | USE | APPROVAL DATE | FAMILY |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 57-101-25G-C4 | C4 | 6.00 | 40.00 | 104.2 | 182.2 | 4 | 2500 | 3,700 | GI | 6/3/2016 | |
| REMARKS: HS20 traffic rated with 1.5 feet of cover required. Secondary pour baffle in center of tank. No septic tank use | | | | | | | | | | | |
| 57-101-30D-C4 | C4 | 6.00 | 48.00 | 104.2 | 182.2 | 2.5 | 3000 | 3,700 | B | 4/4/2014 | |
| REMARKS: HS20 traffic rated with 1.5 feet of cover required. Monolithic baffle. | | | | | | | | | | | |